

TECHNICAL REPORT

- 1 NAME OF WORK : Construction of road via Aafri
- 2 NAME OF ZONE : South-A
- 3 Adm. Sanction : Rs 21.00 Lacs
- 4 Authority : E.E. Jodhpur Development Authority, Jodhpur
- 5 Estimated Cost : Rs 21.00 Lacs
- 6 Necessity of work : The proposed road is to connect Krishna Nagar to Pali Road. It will reduce distance & time for traffic to reach at Pali Road
- 7 Proposal : The following provisions have been taken in the estimate .
a Earth work for embakement protion
b Granular Sub base 150mm. Thick (Compacted) in carriage way and berms on either sides.
c 75mm thick compacted WBM layer (Gr-2) Hand Broken
d 75mm thick compacted WBM layer (Gr-2) Crusher Broken
e Bituminous Macadam 25mm
f Premix Carpet & Seal coat
g NP-4 Pipe 1000mm dia for road crossing
h M-20 Cement Concrete for pipe encasing
- 8 Labour & Material : Labour and material will be arranged by contractor
Gravel & stone ballast shall be brought from approved quarry. Grit and sand shall be brought approved crusher. Bitumen is to be arranged by the contractor himself.
- 9 Machinery & T&P : All Machinery & T&P required for road construction work shall have to be arranged by the contractor himself.
- 10 Agency : The work shall be carried out after calling competative tenders as per rules.
- 11 Rates : The estimate has been framed based on P.W.D Road BSR, 2013 of Jodhpur District

The Estimate submitted for an early Technical sanction.

4
ASSISTANT ENGINEER (South-A)
JODHPUR DEVELOPMENT AUTHORITY,
JODHPUR

[Signature]
EXECUTIVE ENGINEER (South-A)
JODHPUR DEVELOPMENT AUTHORITY,
JODHPUR

+ 2
सन्त
जोधपुर विभागाधिकरण
जोधपुर