

**Full Title of Project :- CONSTRUCTION OF TANDA KOHLA TIKKARI KAWAL KOTHI  
SIDHKOTHI VIA BABA BALAK NATH MANDIR THAPLA DARI KA NAL SIDHYANI ROAD  
KM 0/0 TO 11/340**

**File No. :-**


**Date of Proposal :-**


**DETAIL OF MUCK/DEBRIS TO BE PRODUCED**

**Name Of Work:- CONSTRUCTION OF TANDA KOHLA TIKKARI KAWAL KOTHI  
SIDHKOTHI VIA BABA BALAK NATH MANDIR THAPLA DARI KA NAL SIDHYANI ROAD  
KM 0/0 TO 11/340 TO BE CONSTRUCTED IN DISTRICT MANDI STATE HIMACHAL  
PRADESH.**

**Detail of quantity to be produced and used during the construction of road**

Sr. No.	Description of items	Quantity
1	Total quantity to be produced during construction	49416.00
2	To be used for soling of road (6.5%), wearig of road (6.5%) and filling behind retaining walls of road (20%) total (33%)	16307.00
3	To be used for local use for construction of road average (total 33%)	16307.00
	<b>Total quantity to be used (2+3) :-</b>	<b>32614.00</b>
4	Net quantity to be dumped (1-(2+3))	16802.00
5	Soil factor 40%	6721.00
	<b>G-Total (4+5) in cum :-</b>	<b>23523.00</b>

  
Assistant Engineer  
Chakkar Sub Division  
HPPWD Ner Chowk

  
Executive Engineer,  
Mandi Division No.II  
HPPWD Mandi