

OFFICE OF NAGAR PARISHAD AMARKANTAK DISTT-ANUPPUR (M.P)

Kapildhara Barrage Construction Scheme Amarkantak M.P.

Muck Disposal Scheme

Statement of muck generated in Kapildhara Barrage Construction Scheme in Forest Area

S.No.	Name of Work	Cutting (in Cum)	Bank Filling (in Cum)	Total Filling (in Cum)
1	Kapildhara Barrage Construction	63848.34	75887.17	75887.17
Total :-		63848.34	75887.17	75887.17

Statement of Muck utilization in Kapildhara barrage Construction Scheme in Forest Area

Total Qty. of Muck Generated during Dam Excavation - 63848.34 cum

Total Qty. of E/W required during Dam Construction - 75887.17 cum


Total Qty. of Muck utilized in Dam Construction - 63848.34 cum

Balance Qty. of E/W taken from Borrow Area - 12038.83 cum

Hence No Muck generated during Dam construction

Based on above calculation quantity of cutting is less then quantity of total filling in Dam work and quantity of cutting will be utilized in the filling reach of Dam hence it is certified that No Muck Generated in Dam excavation work.


Sub Engineer
Nagar Parishad Amarkantak
Distt. Anuppur (M.P.)


Chief Municipal Officer
Nagar Parishad Amarkantak
Distt. Anuppur (M.P.)