

GOVERNMENT OF JAMMU AND KASHMIR



PWD (R & B) KASHMIR

**Application For Accord Of
Administrative Approval
For**

**Construction Of Road
From**

**Bindoo, Damdalow Via Bidder To
Tantraypora Zamalgam Verinag
(Agg. Length - 10.00 Kms)**

Under:- CRF

Project Cost:- ₹ ^{1452.52 lacs} 1938.27 Lacs.

Executing Agency:- R & B Division Vailoo

CRF

General Abstract of Cost
Construction Of Road From Bindoo Damdalow Via Bidder To Tantraypora Zamalgam Verinag
(Agg. Length - 10.00 Kms)

S No	Particulars of Items	Unit	Qty	Rate	Amount Rs in Lacs	
1	Earth work in cutting.					
a	Ordinary Rock	Cum	25952.51	275 472.00	71.36 122.50	
b	All Kinds of soils	Cum	77857.52	275 279.00	214.10 217.22	
c	Filling (Rehandelling)	Cum	1317.95	150.00	1.98	
2	Providing and Laying RBM / Nallah Muck	Cum	16500.00	900 1206.00	198.99	148.50
3	Construction of road by way of P/L WBM Grade-II	Cum	2737.50	1500 2572.00	70.41	149.27
4	Construction of road by way of P/L Wet Mix Macadam	Cum	3650.00	2100 2873.00	104.86	76.65
5	Providing & laying 50 mm Thick Bituminous Macadam	Cum	1825.00	8000 10855.0	198.10	146.00
6	Providing & laying 25 mm Thick Semi Dense	Sqm	36500.00	400 500.00	182.50	146.00
7	Construction of 6.00 Mtr span RCC Culvert	No	7	15708.54 2092548	146.48	109.95
8	Construction of 3 Mtr Span RCC Culvert	No	6	981519 1308274	78.50	58.89
9	Construction of 1 Mtr RCC Box type culvert	No	3	349816 429641	42.89	10.25
10	Providing and laying R.C.C Spun pipes	Rm	75.00	9017	6.76	
11	Construction of cement concrete R Wall	Rm	1500	113416 17120	256.79	170.19
12	Construction of cement concrete B Wall	Rm	1100	7029 10517	115.68	77.31
13	Construction of cement concrete drain	Rm	2250	3089 4273	96.14	69.50
14	Construction of Kacha Drain	Rm	4500	135 99	6.08	4.45
15	Development of Berm by way of P/L Khakh Bajree	Cum	2025.00	650 866	17.54	13.16
16	Provision for road furniture	Km	10	25000	2.50	
Total					4835.92	1376.82
Add 3.00 % Contingencies					55.08	41.30
Sub Total					1891.00	
Cost of devising & Quality(1%)					18.91	13.76
'Provision for quality Control(1%)					18.91	13.76
'Establishment Charges(0.50%)					9.45	6.88
G Total					1938.27	
Say Rs					1938.27 Lacs	1452.52 Lacs.

Asstt. Executive Engineer
R & B Sub Division Kokernag

Executive Engineer
R & B Division Vailoo

Superintending Engineer
R & B Circle Anantnag / Kulgam


Chief Engineer
PW(R&B) Department Kashmir

Salient Features of the Scheme.

Name of Scheme :-

Construction Of Road From Bindoo Damdalow Via Bidder To
Tantraypora Zamalgam Verinag (Agg. Length - 10.00 kms)

- | | |
|----------------------------------|---------------------|
| 1. Name of State | : Jammu And Kashmir |
| 2. Name of District | : Anantnag |
| 3. Name of Constituency | : Kokernag |
| 4. Road way Width Existing | : Nil. |
| 5. Proposed Road way width | : 3.65 Mtr |
| 6. Carriageway Width Existing | : Nil |
| 7. Existing Status | : Earthen track |
| 8. Proposed Status | : Macadamization |
| 9. Proposed Carriageway width | : 3.65 mtr |
| 10. Population to be Benefited:- | : 19000 Souls |
| 11. Existing Pavement Thickness | : -Nil |
| 10. Proposed Pavement Thickness. | : 475 mm |


Assistant Executive Engineer,
R & B Sub- Division Kokernag


Executive Engineer,
R & B Division Vailoo