MODEL COST ESTIMATES FOR COMPENSATORY AFFORESTATION

ON ALLOTED NON FOREST LAND

UNIT:

PERIMETER:

LABOUR RATE:

50 Ha 60 M/Ha. Rs.259/Day in Rs./Ha.

COST ESTIMATE: ADVANCE ACTION (0 YEAR)

S.No	LIENS	RATE (Rs.)	LABOUR COMPONENT	, MATERIAL COMPONENT	TOTAL
1	Collection of Basic Datas for Microplanning and carrying joint forest management activities.		604.33	50.29	-
2	Survey of area, lay out of contour trenches, burrowpits ar making of segments / plots	1 463/ha	475.44	30.29	526
3	Fencing by stone wall and or by ditch.		0.00	. 0	
	a.) Stone wall fencing 1.20m high 0.80m at base & 0.60 at top (on an average 30m/ha.)	225/rmt	7770.00	0	7770
-	b.) Ditch fencing 1.20m deep, 1.50m wide at top & 0.90m abottom (on an average 30m/ha.)	et 245.16/rmt	8466.75	0	8467
4	Cost of raising 1210 seedlings in nursery.	3.93/- per	3492.24	1730.19	5222
5	Digging of 500 pits size: 0.45x(.4+.5/2)2	17.59/ pit	10128.97	0	10129
5	Digging up 400 rmt Staggered Contour Trenches 45x45cm cross section on middle slopes and V-ditch as per site requirement	28.28/rm1	13025.39	0	13025
7	Construction of 15 mt. long contour dykes of 30X30 cm. cross section on upper slopes and sowing of suitable thornshrub species seeds along its innerside		526.51	0	527
S	Treatment of Nallas by construction series of Checkdams of dry ramdom rubble/earthan/brushwood	Prorata	755.11	0	755
9	Construction of the pillars of appropiate size and fixing of iron pipe gate with four square column	Prorata	82.69	97.37	180
10	Construction of approach road and inspection path	Prorata	285.75		
11	Watch and ward @15325 per month for 4 months	Prorata	1490.77	0	1491
12	Construction of Thatched cattle guard hut.	Prorata	145,92	70.1	1
1.3	Cost of grass and other seeds	Prorata	0.00	78.11	224
14	Labour aminities	Prorata	94.85	242.89	243
	Purchase of tools and plants	Prorata	0.00	85.6	180
.6	Purchase or construction of water storage tank.	Prorata	81.47	110.21	110
?	Purchase of signboards and their flxing	Prorata		48.15	130
.8	Misc. and unforeseen expenses including running of	Prorata	32.83	92.02	125
	vehicles		154.43	162.64	317
9 ,	TOTAL YEAR 0		47613.44	2747.76	7000
_	TOTAL			-, 71.16	50361
	4				5036 55397

While.

30,

YEAP I (PLANTING YEAR)

ditc 1/4	yout of of staggered/continuous contour trenches, V-tches, contour dykes and pits etc. by contour survey in 4th area ligging of 600 pits of size 0.45 (4+5/2)*2 Cum construction of silt detention dams/smal anicut/check ams, etc. Isaintenance of 1210 seedling in nursery estoration of natural regeneration by making crescent hapad mounds on the lower slopes of seedling and sapling and making ring trenches around the natural trees/shrubs. 150 plant/ ha) Sowing of pellats of grass/pieces of seed mud cakes of grass eeds between row of pits by ploughing and furrowing. Sowing/dibbling of seeds of shurb species on the mounds of staggered/continuous contour trenches, "V" ditch and ditch fencing including pretreatment of seeds (370 rmt.) Sowing of seeds of shrub spp. on 60 mt. "V" ditch Transportation of 1100 plants from nursery to planting site Planting of 1100 seedlings including Refilling of pits Making of 1100 crescent shaped mounds below planted sapling after planting and dibbling 2 or 3 seeds of shrub species on the mound.	0.59/ rmt.	81.47 12154.76 3247.84 2554.74 707.69 1011.68 238.33 42.56 1714.51 5189.73 4534.32	0 255.73 341.33 0 62.06 11.77 3.21 68.48	1215 350 289 70 107 25 4 178 519 453
Coldada	construction of silt detention dams/smal anicut/check ams, etc. Italiantenance of 1210 seedling in nursery estoration of natural regeneration by making crescent hapad mounds on the lower slopes of seedling and sapling and making ring trenches around the natural trees/shrubs. 150 plant/ ha) Sowing of pellats of grass/pieces of seed mud cakes of grass eeds between row of pits by ploughing and furrowing. Sowing/dibbling of seeds of shurb species on the mounds of staggered/continuous contour trenches, "V" ditch and ditch fencing including pretreatment of seeds (370 rmt.) Sowing of seeds of shrub spp. on 60 mt. "V" ditch Transportation of 1100 plants from nursery to planting site Planting of 1100 seedlings including Refilling of pits Making of 1100 crescent shaped mounds below planted sapling after planting and dibbling 2 or 3 seeds of shrub	Prorata 2.11/ plant 4.1/plant Prorata 0.59/ rmt. Prorata 1.41/plant 3.58/plant	3247.84 2554.74 707.69 1011.68 238.33 42.56 1714.51 5189.73	255.73 341.33 0 62.06 11.77 3.21 63.48	289 70 107 25 4 178 519
dai dai	estoration of natural regeneration by making crescent hapad mounds on the lower slopes of seedling and sapling and making ring trenches around the natural trees/shrubs. 150 plant/ ha) sowing of pellats of grass/pieces of seed mud cakes of grass eeds between row of pits by ploughing and furrowing. sowing/dibbling of seeds of shurb species on the mounds of staggered/continuous contour trenches, "V" ditch and ditch rencing including pretreatment of seeds (370 rmt.) Sowing of seeds of shrub spp. on 60 mt. "V" ditch Transportation of 1100 plants from nursery to planting site Planting of 1100 seedlings including Refilling of pits Making of 1100 crescent shaped mounds below planted sapling after planting and dibbling 2 or 3 seeds of shrub	2.11/ plant 4.1/plant Prorata 0.59/ rmt. Prorata 1.41/plant 3.58/plant	2554.74 707.69 1011.68 238.33 42.56 1714.51 5189.73	341.33 0 62.06 11.77 3.21 63.48	289 70 107 25 4 178 519
8 Sc st fee 9 Si 10 T 11 P 12 N 13 S 14 A 15 N 16 (6 17)	estoration of natural regeneration by making crescent hapad mounds on the lower slopes of seedling and sapling and making ring trenches around the natural trees/shrubs. 150 plant/ ha) lowing of pellats of grass/pieces of seed mud cakes of grass eeds between row of pits by ploughing and furrowing. Sowing/dibbling of seeds of shurb species on the mounds of staggered/continuous contour trenches, "V" ditch and ditch encing including pretreatment of seeds (370 rmt.) Sowing of seeds of shrub spp. on 60 mt. "V" ditch Transportation of 1100 plants from nursery to planting site Planting of 1100 seedlings including Refilling of pits Making of 1100 crescent shaped mounds below planted sapling after planting and dibbling 2 or 3 seeds of shrub	Prorata 0.59/ rmt Prorata 1.41/plant 3.58/plant	707.69 1011.68 238.33 42.56 1714.51 5189.73	62.06 11.77 3.21 68.48	107 25 4 178 519
Sh and (1)	hapad mounds on the lower slopes of seedling and sapling and making ring trenches around the natural trees/shrubs. 150 plant/ ha) dowing of pellats of grass/pieces of seed mud cakes of grass eeds between row of pits by ploughing and furrowing. Sowing/dibbling of seeds of shurb species on the mounds of staggered/continuous contour trenches, "V" ditch and ditch encing including pretreatment of seeds (370 rmt.) Sowing of seeds of shrub spp. on 60 mt. "V" ditch Transportation of 1100 plants from nursery to planting site Planting of 1100 seedlings including Refilling of pits Making of 1100 crescent shaped mounds below planted sapling after planting and dibbling 2 or 3 seeds of shrub	Prorata 0.59/ rmt Prorata 1.41/plant 3.58/plant	1011.68 238.33 42.56 1714.51 5189.73	62.06 11.77 3.21 63.48	107 25 178 515
Se S	seeds between row of pits by ploughing and furrowing. Sowing/dibbling of seeds of shurb species on the mounds of staggered/continuous contour trenches, "V" ditch and ditch fencing including pretreatment of seeds (370 rmt.) Sowing of seeds of shrub spp. on 60 mt. "V" ditch Transportation of 1100 plants from nursery to planting site Planting of 1100 seedlings including Refilling of pits Making of 1100 crescent shaped mounds below planted sapling after planting and dibbling 2 or 3 seeds of shrub	0.59/ rmt. Prorata 1.41/plant 3.58/plant	238.33 42.56 1714.51 5189.73	3.21 63.48	25 4 178 519
9 So To	staggered/continuous contour trenches, "V" ditch and ditch encing including pretreatment of seeds (370 rmt.) Sowing of seeds of shrub spp. on 60 mt. "V" ditch Transportation of 1100 plants from nursery to planting site Planting of 1100 seedlings including Refilling of pits Making of 1100 crescent shaped mounds below planted sapling after planting and dibbling 2 or 3 seeds of shrub	Prorata 1.41/plant 3.58/plant	42.56 1714.51 5189.73	3.21 63.48	178
10 T 11 P 12 N 5 S 13 S 14 A 16 (17)	Planting of 1100 plants from nursery to planting site Planting of 1100 seedlings including Refilling of pits Making of 1100 crescent shaped mounds below planted sapling after planting and dibbling 2 or 3 seeds of shrub	1.41/plant 3.58/plant	1714.51 5189.73	68.48	178 519
11 P 12 N s s 13 S c 14 A i 15 N 16 (Planting of 1100 seedlings including Refilling of pits Making of 1100 crescent shaped mounds below planted sapling after planting and dibbling 2 or 3 seeds of shrub	3.58/plant	5189.73	0	51
12 N s s s s s s s s s s s s s s s s s s	Making of 1100 crescent shaped mounds below planted sapling after planting and dibbling 2 or 3 seeds of shrub				
13 S C C 14 A i 15 N 16 (17 N)	sapling after planting and dibbling 2 or 3 seeds of shrub	3.16/plant	4534.32	. 0	45
14					
15 16 (17)	Spot watering $\&$ application of insecticides in 1100 plants in case of advance planting.	3.16/plant	4012.68	0	40
16	Additional watering in case of long drought spell with insecticide.	3.57/plant	4012.68	. 0	40
17	Weeding and hoeing of 1100 plants in 2 times.	2.03/plant	9041.90	, 0	90
	One additional hoeing of 1100 plants.	1:93/ plant	2581.49	.0	25
	Wedding and hoeing on staggered/ continuous contour trenches and 'V' ditch including Singling/spacement in the	Prorata	813.48	0	. 8
	Purchase of insecticide and Fertilizers for 1100 plants.	0.82/plant	0.00	906.29	9
	Raising of 110 seedilings in nursery for casualty replacement in year-2 (10% of 1100)	3.93/seedling	317.37	157.29	4
-	Watch and ward @15325 per month for 12 months	prorata	4472.31	0	44
21	Special protection of frost tender species.	Prorata	42.56		
22	Labour aminities.	Prorata	200.63		
24	Repairs of fencing. Repairs of check dams.	193/hact.	237.11	9.63	
25	Micellaneous and unforeseen expenditure.	Prorata	86.33	THE RESERVE THE PERSON NAMED IN COLUMN TWO IS NOT THE OWNER.	
	and unforeseen expenditure.	Prorata	160.51		2
26		1	57456.66	2071.52	595
	TOTAL YEAR Administrative charges 10%				59

Alle.

30

	First Year Maintenance (year 2)	,			
1	Collection of datas regarding impact assesment and strengthening Joint Forest Management.	Prorata	0.00	72.76	73
2	Maintenance of 110 Seedling in nursery for casualty replacement in 2nd year	2.15 /plant	232.25	31.03	263
3	Casualty replacement 110 plants including redigging of pits, transportation planting, watering	11.55/plant	1382.55	69.55	1452
4	Sowing/dibbling of seeds of shurb species on the mounds of staggered/continuous contour trenches, "V" ditch and ditch fencing including pretreatment of seeds (185 m.)	0.61/ rml.	124.03	5.35	129
5	Weeding and Hoeing in 1200 plants in pits two times	3.57/plant	9041.90	0	9042
6	Wedding and hoeing on staggered/ continuous contour trenches and 'V' ditch including Singling/ spacement in the line sowing. (185 rmt.)	3.82/plant	814.69	0	815
7	Repair of fencing	216/-ha.	237.11	9.63	247
8	Repairing of Check dams	Prorata	165.37		
9	Pruning of Trees species to boost up the growth	Prorata	251.70	11.77	177
10	Wages of Chowkidar @ Rs.15325/ month (only applicable to work chage employee)	prorata	. 4472.31	12.84 0	265 4472
11	Misc. and unforeseen expenditure	prorata	147.13		<i>P</i>
	TOTAL YEAR 2	1.	1 1 3	67.41	215
12	Administrative charges 10%		16869.05	280	17149
	TOTAL		1	, , , ,	1715
	SUBSEQUENT MAINTENANCE (YEAR 3 TO 1	2)			40004
1	Collection of datas regarding impact assesment and strengthening Joint Forest Management.	Prorata	0.00	72,76	73
2	Sowing/dibbling of seeds of shurb species on the mounds of staggered/continuous contour trenches, "V" ditch and ditch fencing including pretreatment of seeds (185 m.)	0.61/ rmt.	124.03	5.35	129
3	Repair of fencing	216/hact	237.11		
4	Repairing of Check dams	Prorata		9.63	247
5	Pruning of Trees species to boost up the growth		8.51	6.42	15
	· .	Prorata	125.24	4.28	130
6	Wages of Chowkidar @ Rs. 15325/- month (only applicable to work chage employee)	prorata	4472.31	0	4472
7	Maintenance of Vehicles	prorata	115.52	100.58	216
	TOTAL YEAR 3.		5082.72	199	216
	Administrative charges 10%			133	5282
				Total	528
	GRAND TOTAL				5810
_	OYear First Year	55397		*1	
	Second Year	65481			
	Third Year	18864			
	Fourth Year	5810			
	Fifth Year	5810 5810			
	Sixth Year	5810			(*
	Seventh Year	5810			
	Eighth year	5810			
	Ninth Year Tenth Year	5810			
	Eleventh Year	5810			
	Twelth Year	5810			_
	Total	5810		•	
		197842			

197842 198000

डिवप्र डिप् चेन संरक्षक (प्रशासन) प्रधान मुख्य वन संरक्षक प्रशिक्षण, अनुसंधान, शिक्षा एवं प्रकार

(अभर सिंह गोठ गरा) मुख्य वन स्रंखक (आयोजना), राजस्थान, प्रमृत्य

. भारतिकाम्प्रिकानिकाम्प्रिकाम्प्रिकाम्