

Name Of Project Agron Band To Awalanghat Moter Road

Performa for comparison between identified alignments

Sl.No	Variables	Alignment No-1	Alignment No-2
1	Topography	Hilly	Hilly
2	Length of Road	17.00km	17.00km
3	Bridging requirement No. and Length	01 no 80 Meter	041no 80 Meter
4	Geometric	-	-
	(a) Gradients	1:22F,1:24F	1:22F,1:24F
	(b) Curves, H.P Bends	10 no	10NO
5	Existing Means of communication, mule path, jeep, Tracks etc.	Bridle Path multi track	Bridle Path multi track
6	Right of way, bringing out. construction on account of built up areas, monuments and other structures.	nill	Nill
7	(a) Terrain & Soil Condition.	17.00km	17.00km
	(vi) Cliffs and gorges.(vii) Drainage characteristics of the area including suscepibility to flooding .(viii) General elevation of the road indicating maximum and minimum height negotiated by main ascends and descends.(ix) Variations extants and types.	Nill Good 800-1100mts	Nill Good 800-11 00mts
8.	Climate Condition:(a) Temperature Monthly max. & min. reading.(b) Rainfall data average annual peak intensities monthly distribution (to the extent available) .(c) Snowfall data average annual peak intensities monthly distribution (to the extent available) .(d) Wind direction and velocities.(e) Fog Condition.(f) Exposure to sun.(g) Unusual weather condition like cloud brust etc.	(a)Max40,min10 (b)june-september (c)No snow area North-east Minor damage&mayoccur during rainy season	(a)Max40,min10 (b)june-september (c)No snow area North-east Minor damage&mayoccur during rainy season
9.	Facilities resources. (a) Landing ground. (b) Dropping Zone.	(a)Nill (b)Nill (c)Local food grain available as par	(a)Nill (b)Nill (c)Local food grain available as par

2.4


	(c) Food stuffs. (d) Labour local availability and need for import. (e) Construction material (Timber, Bamboo, Sand, Stone, Shingle etc. extent of their availability and lead involved.	(d) Locals & Napolis (e) stone local available sand & grit from haldwani	(d) Locals & Napolis (e) stone local available sand & grit from haldwani
10.	Value of land, agricultural land, Irrigated land, built up land, forest land etc,	Agricultural-34.58 Lac Forest land-72.51 Lac	Agricultural-34.58 Lac Forest land-72.51 Lac
11.	Approximate Const. Cost.	452.80 Lac	452.80 Lac
12.	Access point indicating possibility of induction of equipment.	Pithoragarh-90 km	Pithoragarh-90 km
13.	Period required for construction.	1 year	1 year
14.	Strategic Consideration.	nill	nill
15.	Important villages, towns and markets centers to be connected.	Pali, Pokhari, Jatudi, Boyal, Sungarnola, Agron	Pali, Pokhari, Jatudi, Boyal, Sungarnola, Agron
16.	Recreational potential.	May development by this alignment	May development by this alignment
17.	Economic Factors: (a) Population served by the alignment. (b) Agricultures and economic potential of the area.	Agricultures and other local product Total population 1974 S.C population-800	Agricultures and other local product Total population-1974 S.C population-800
18.	other major development projects being taken up electric projects etc.	Nill	nill
19.	(i) Misc. Such as camping sites (ii) Law and other problem (iii) Royalty	nill	nill
	(iv) Availability of contractors for collection and carriage of construction material (v) working period available for construction of work.	Available 12-months	Available 12-months
20.	Total No. of trees to be removed .	427	427


2-4


21.	Average Density of forest cover .		
22.	(a) Merits (b) Demerits	1. All Villagers are agree with this alignment 1. More nap land will be effected	1. mostly villagers are not agree with this alignment More forest land and trees will be effected
23.	Total No. of Demerits	-	-

RECOMMENDATIONS:

Alignment no. (1) Recommended for approval being more economical, useful & technically feasible.


Assistant. Engineer/J.E


सहायक अभियन्ता
अस्थाई बन्द लोड नि० वि०
बेरीनाथ (पिथौरागढ़)


प्रमुख अभियन्ता
अस्थाई बन्द, पो० नि० वि०
बेरीनाथ (पिथौरागढ़)


17/03/2019