## Title-: C/O link Road From Bharari to Padhya Mata Mandir RD 0/0 to 1 200,

MUCK MANAGEMENT PLAN (MMP)

Sr.	Description	1	
1	Total Quantity of Muck being produced	Quantity 3000.00	
	Deduction for useful stone as required under the along the		
2	the Community Executive Engineer of Design 1/2 2000 as	1000.00	
3	The summer of the period of th	2000.00	
4	: " site will swell factor (a) 40% 1 40 Å (B)		
	Total (sr.3+4)	800.00	
5	mark to be used iii Floject-	2800.00cum(B	
(i)	Deduction of material required for the construction of dumping place in dry masonry wall/Edge wall/R Wall and B/wall @ 20% of (P)	560.00	
ii)	construction @5% of (B)	140.00	
	Less for material /Muck required for the construction of the proposed road on the analogy of half cutting half filling @ 15% of (B)	420.00	
	Total :- (i)+(ii)+(iii)	1120.00(C)	
6	Net material/Muck to dumped in dumping site (B-C) in Cum	1680.00 cum	

Proposed dumping sites

Material/Muck left at the site which required carriage for the proper dumping at the recognized site as per the instructions of forest and environment Ministry reinforced by various judgments of the Apex Court Govt. of india.


Sr. No.	Dumping Site No.	Kh no.	Design Annexed Yes/No.	Capacity
1.	Ì	3/1	yes	2100.00
			Total	2100.00 Cum

Executive angineer, Shimla Division No.1 HP.PWD. Shimla-3

Gs

Divisional Forest Officer Shimla Forest Division

SHIMLA



Assistant Engineer, Shimla Sub - Division No. 1 H.P.P.W.D., Shimla - 3 Lead Q.P. P. W. L. Spranke