

DETAIL OF MEASUREMENT**Name of work :- Construction of motorable Link road from Rajera (Bhaniya) Bailly KM. 0/0 to 4/500****(SH:- CONSTRUCTION OF WIRE CRATES)**

S.No	Item	Dumping site	LxBxH	Quantity
1	Earthwork in excavation for structures as per drawing and technical specifications clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with	DS-I	110x1/2x1.25x1.25	85.94
		DS-II	110x1/2x1.25x1.25	85.94
		DS-II	110x1/2x1.25x1.25	218.75
			Total	390.63
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	DS-I	2x110x1.25x1.25	343.75
		DS-II	2x110x1.25x1.25	343.75
		DS-III	2x280x1.25x1.25	875.00
			Total	1562.50


Assistant Engineer,
Chamba Sub Division, No. II
HP.PWD., Chamba

"ABSTRACT OF COST"

Name of work :- Construction of motorable Link road from Rajera (Bhaniya) Bailly KM. 0/0 to 4/500

(SH:- CONSTRUCTION OF WIRE CRATES)

S.No	Item	Qty	Rate	Unit	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable materials Ordinary soil Upto 3 m depth	390.63	128.15	Per cubic metre	50059.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301	1562.50	1458.40	Per cubic metre	2278750.00
Total					2328809.00

Assistant Engineer,
Chamba Sub Division, No.II
HP.PWD. Chamba


Executive Engineer,
Chamba Division,
HP.PWD. Chamba