

DETAIL OF MEASUREMENT

Name of Work: C/o Thachdhar Naloti road km. 0/000 to 8/000 (SH: C/o dumping places).

Sr. No.	Description of items	Unit	L	W	H/D	Qty.
1	Excavation in earth work etc.	1	75.26	2.00	0.45	67.73
		1	59.64	2.00	0.45	53.68
	Total					121.41
2	Wire crate made of GI wire filled with boulders with square cut faces etc. 1st to 4th layer (80 no. in each layer)	1	75.26	1.80+0.90/2	4.80	487.68
		1	59.64	1.80+0.90/2	4.80	386.47
	Total					874.15

Handwritten signature

Handwritten signature
Executive Engineer
HPPWD Division
Seraj at Janjehli

ABSTRACT OF COST

Name of Work: C/o Thachdhar Naloti road km. 0/00 to 8/00 (SH: C/o dumping places)

Sr. No.	Description of items	Unit	Qty.	Rate	Amount
1	Excavation in earth work and disposal of all excavated earth upto a lead of 20 mtr. and lift upto 1.50 mtr. disposed earth to be leveled and neatly dressed (PW+JW 50% each)	cum	121.41	69.25	8408.00
2	Wire crate made of GI wire filled with boulders with square cut faces against the wire (wire crate to be measured and paid for separately).	cum	874.15	287.60	251406.00
	Total				259814.00

Author

by ammp
Executive Engineer
HPPWD Division
Seraj at Janjehli.