


**CERTIFICATE/ UNDERTAKING FOR MITIGATION MEASURES FOR SOIL
EROSION**

Certified that during the execution period of the proposed road i.e. Construction of link road from DhuraSapar to Purkhara (Portion Kutplyana to Purkhra) Km 4/040 to 11/540 retaining structures such as retaining walls and breast walls in Concrete as well as in wire crates (gabion walls) will be constructed in the areas where land slide/ soil erosion is likely to occur. Also, Longitudinal drains and cross water drains (Hume pipe culverts, slab culverts and solid causeways) will be constructed for proper channelization of rain water which will reduce chances of soil erosion. And after the construction period labour and machinery will be deployed for maintenance of longitudinal drains and well as Cross drainage structures.


Executive Engineer
Chowari Division
HPPWD Chowari