

ಕರ್ನಾಟಕ ನೀರಾವರಿ ನಿಗಮ ನಿಯಮಿತ (ಕರ್ನಾಟಕ ಸರ್ಕಾರದಉದ್ಯಮ)

KARNATAKA NEERAVARI NIGAM LIMITED

(A Karnataka Government Enterprise)
Office of the Executive Engineer, KNNL GRBCC Div No 3 Gokak.
Fax & Phone No 08332-225213 email: knnlgrbccd3.gokak@gmail.com

Sub: Diversion of 575.11 Ha of Forest land for the construction of dam across Markandeya River and ancillary infrastructure in forest lands of Gokak, Godachinamalki, Konnur and Mavanura villages in Gokak and Hukkeri Taluks, Belagavi District for storing 6 TMC of water under Ghatti-Basavanna Drinking Water Supply Project by Karnataka Neeravari Nigam Limited, Govt. of Karnataka.

| Sl. No | Observations | Clarification |
|-----------|---|---|
| 1 | Specify the contours for calculating submergence | 618 m contour has been considered for finalizing the submergence. As per the suggestion, KML file containing FRL of 616 m, 618 m and 620 m has been uploaded. |
| 2 | Why are the non-essential components like guest house and Dam View Point included in the forest land requirement for the project? Please provide the details. | Since the proposed dam is in the forest land and also the height of the dam being very high, it is necessary to provide a guest house including watch tower at higher land where submergence and spillway portion can be watched continuously. On study of Toposheet, the highest land available is on the right flank where the above activity can be controlled. Hence, Guest House and Dam View Point is located at that point. The proposed location falls under forest area. Alternative locations are tried for this watch tower and dam View Point which are not feasible. Hence, the same is proposed. |
| 3 | Details of extra works/activities proposed in the components named 'Dam View Point' and 'Utility'. | Dam View Point is an open area with a watch tower for controlling the operations. Utility is with a small security room with provision for toilet blocks. |
| 4 | Whether any underground components such as Tunnel is also part of the project? If yes, please provide the details thereof. | There are no underground components envisaged under the project. |

Executive Engineer
Karnataka Neeravari Nigam Limited,
GRBCC Division No.3,
Gokak-591307, Belgaum.