

Construction of BT road KALAPATTA ASNAWAR ROAD TO KARWALA

Earthwork

Km. 0/0 to 3/50

S.No.	Chainage	C/S Area (In Sqm.)		Quantity in (Cum.)	
		Cutting	Filling	Cutting Volume	Filling Volume
1	0	0	0.853	0	0
2	25	0	1.724	0	32.215
3	50	0	2.767	0	56.145
4	75	0	3.541	0	78.858
5	100	0	5.068	0	107.616
6	125	0	5.661	0	134.115
7	150	0	5.764	0	142.815
8	175	0	4.927	0	133.64
9	200	0	2.111	0	87.977
10	225	0	1.924	0	50.439
11	250	0.017	0.893	0.214	35.216
12	275	0	1.77	0.214	33.286
13	300	0	4.631	0	80.01
14	325	0	3.941	0	107.152
15	350	0	5.201	0	114.277
16	375	0	5.181	0	129.777
17	400	0	5.146	0	129.09
18	425	0	4.746	0	123.652
19	450	0	3.451	0	102.465
20	475	0	3.046	0	81.215
21	500	0	3.036	0	76.027
22	525	0	2.571	0	70.09
23	550	0	1.866	0	55.465
24	575	0	2.599	0	55.815
25	600	0	3.727	0	79.077
26	625	0	2.315	0	75.527
27	650	0	2.128	0	55.54
28	675	0	1.901	0	50.365
29	700	0.31	0.333	3.874	27.925
30	725	0	1.192	3.874	19.062
31	750	0	3.07	0	53.277
32	775	0	4.373	0	93.04
33	800	0	4.431	0	110.052
34	825	0	3.914	0	104.315
35	850	0	4.742	0	108.202
36	875	0	5.705	0	130.59
37	900	0.247	0.714	3.093	80.233
38	925	0	4.856	3.093	69.62
39	950	0	3.541	0	104.965
40	975	0	3.596	0	89.215
41	1000	0	3.436	0	87.902
42	1025	0	2.986	0	80.277
43	1050	0	3.346	0	79.152
44	1075	0	3.296	0	83.027
45	1100	0	3.501	0	84.965
46	1125	0	4.021	0	94.027
47	1150	0	3.101	0	89.027
48	1175	0	3.507	0	82.602
49	1200	0	3.323	0	85.377
50	1225	0	3.269	0	82.402
51	1250	0	3.395	0	83.302
52	1275	0	3.516	0	86.39
53	1300	0	3.522	0	87.977

54	1325	0	3.063	0	82.315
----	------	---	-------	---	--------

55	1350	0	4.174	0	90.465
56	1375	0	2.721	0	86.19
57	1400	0	3.815	0	81.702
58	1425	0	3.609	0	92.802
59	1450	0	3.308	0	86.465
60	1475	0	3.062	0	79.627
61	1500	0	3.156	0	77.727
62	1525	0	2.885	0	75.515
63	1550	0	2.549	0	67.927
64	1575	0	1.903	0	55.652
65	1600	0	2.552	0	55.69
66	1625	0	2.096	0	58.102
67	1650	0	2.715	0	60.14
68	1675	0	2.739	0	68.177
69	1700	0	2.718	0	68.215
70	1725	0	2.347	0	63.315
71	1750	0	1.891	0	52.977
72	1775	0	1.515	0	42.577
73	1800	0	1.559	0	38.427
74	1825	0	1.713	0	40.902
75	1850	0	2.022	0	46.69
76	1875	0	1.726	0	46.852
77	1900	0	2.55	0	53.452
78	1925	0	3.514	0	75.802
79	1950	0	3.913	0	92.84
80	1975	0	4.412	0	104.065
81	2000	0	3.256	0	95.852
82	2025	0	4.682	0	99.227
83	2050	0	3.293	0	99.69
84	2075	0	3.799	0	88.652
85	2100	0	3.495	0	91.177
86	2125	0	4.546	0	100.515
87	2150	0	4.277	0	110.29
88	2175	0	3.858	0	101.69
89	2200	0	4.109	0	99.59
90	2225	0	3.77	0	98.49
91	2250	0	4.261	0	100.39
92	2275	0	2.031	0	78.653
93	2300	0	2.065	0	51.205
94	2325	0	2.449	0	56.433
95	2350	0	1.074	0	44.047
96	2375	0	1.088	0	27.032
97	2400	0	0.708	0	22.451
98	2425	0	2.53	0	40.478
99	2450	0	1.059	0	44.871
100	2475	0.006	1.81	0.071	35.872
101	2500	0	1.843	0.071	45.668
102	2525	0	0.783	0	32.829
103	2550	0	0.559	0	16.784
104	2575	0	0.966	0	19.064
105	2600	0	1.108	0	25.919
106	2625	0.172	1.211	2.152	28.989
107	2650	0	3.199	2.152	55.129
108	2675	0	5.135	0	104.177
109	2700	0	3.631	0	109.577
110	2725	0	2.606	0	77.965
111	2750	0	3.639	0	78.065
112	2775	0	3.978	0	95.215
113	2800	0	2.626	0	82.552
114	2825	0	3.099	0	71.56
115	2850	0	3.035	0	76.673

116	2875	0	2.966	0	75.017
-----	------	---	-------	---	--------

117	2900	0	2.637	0	70.045
118	2925	0	2.966	0	70.038
119	2950	0	3.039	0	75.054
120	2975	0	3.559	0	82.474
121	3000	0	3.106	0	83.314
122	3025	0	3.077	0	77.286
123	3050	0	3.896	0	87.163
Total				18.808	9246.561