

DETAILED NOTE ON THE PROJECT

INTRODUCTION:-

GSPC Gas Company Limited (GSPC GAS), having the registered office of the company situated in the State of Gujarat at Block No. 15, 2nd Floor, Udyog Bhavan, Sector-11, Gandhinagar.

GSPC Gas Company Limited (GSPC GAS) is currently in the business to setup Piped Natural Gas network (PNG) to provide PNG for residential consumers as well as commercial units and CNG Station in various cities of Gujarat State.

GSPC Gas Company Limited is planning to lay a 30/15 Cm Steel & 12.5/9 cm dia PE PNG pipeline to connect various villages in Jamnagar & Surrounding Area to provide natural gas to enroute industries/ consumers in Jamnagar District, Gujarat State.

As a part of GSPC Gas project approximately 35 Km long 30/15 Cm Steel & 12.5/9 Cm dia PE PNG pipeline in Jamnagar & Surrounding Area Gas Distribution Network (Lalpur Spurline, Reliance Green Spurline, Sikka Spurline, Bed Spurline, Sapar Spurline & Khambhaliya Spurline) is required to be laid in Jamnagar District, Gujarat State. It will be laid underground with a minimum clear cover of 1.2 meter.

One of the main objects to be pursued by the company on its incorporation is to lay, design, construct, fabricate, install and maintain gas process and gas manufacturing plants, gas installation including gas storage, machinery apparatus, pipes, valves fillings, meters and other allied accessories necessary and useful for the manufacturer, supply and destination of gas and energy.

Investigation: -

The route has been carefully selected to minimize total length of the pipeline and forests based on desktop study and reconnaissance survey carried out by consultants M/s. Secon Pvt. Ltd.

The Right of Use (RoU) for forest area is proposed as a minimum of 1.0, 0.5 & 0.4 mts. width (which is the minimum requirement).

The alignment is selected in such a way that while crossing the area under forest cutting of trees is minimized / avoided.

Design:-

The entire pipeline will be designed to withstand a Maximum Allowable Operating Pressure (MAOP) of 4 and 49 bars for MDPE & Steel pipeline respectively. The design code that generally will be followed would be ANSI B31.8 and PNGRB Technical Standard for CGD.

Pipe material: -

Pipe material would be Petroleum Institute (API) grade Steel & Indian Standard MDPE material, inspected at factory through third party inspection agency. All valves would be full-bore ball. All pipe fittings would be matching type and class.

Corrosion protection: -

The pipeline will be coated with 3 layers of Polyethylene (PE). All field joints will be coated with Raychem sleeve or equivalent followed by Holiday detection to ensure continuity of corrosion protective layer. A suitable, impressed current cathodic protection system will be provided as an additional protection to the pipeline.

A competent pipe laying contractor will be engaged for this work. The project will be monitored at site and office levels through latest project management software like MS.

The pipeline will be constructed as per the latest international standards like ANSI B31.8 and ASME. All good engineering practices will be followed during fabrication and laying of the pipe including usage of approved welding procedures, qualified welders and well identified consumable. Radiography of weld joints will be carried out as per applicable standard. Periodic pigging of the pipeline during construction will ensure expeditious completion and smooth commissioning. Entire execution will be supervised by a competent Third Party Inspection (TPI) agency that will in turn test and certify the pipeline trial commissioning will also be done under the supervision of this TPI.

Investments:-

The estimated total cost of the project is Rs. 30 Crore (Approx.)

Time Schedule:

The completion schedule for this project is 2014-2015