

**Note seeking permission for Temporary Ropeway which includes erection of 20 Nos Towers & a Ropeway within Forest land for approaching the weir site**

Based on the suggestion of the Forest Dept. during the joint inspection held on 17.11.18, the approach road to the weir site has since been deleted and a temporary ropeway (1000m long & 4.5 m wide) has been proposed.

**Salient Features of the Ropeway Proposal**

Length	:	1000 m
No. of Steel Towers	:	20 Nos @ a span of
50 m each. Width of Ropeway	:	4.5 m
Size of Tower	:	2x2 m

- \* The Ropeway is to be used for sending out the tunnel muck outside the RF area and to bring in the required construction materials to the site.
- \* 50Nos of Trees would have to be felled for the construction of the Ropeway.
- \* All the steel towers as well as the Ropeway can be dismantled once the construction works are over.
- \* After construction works are over, the area of 4500m<sup>2</sup> of Forest land acquired for construction purposes will be handed over back to the Forest Department.