

Title:- Gravity Zip Ropeway From Nag Devta to Kufri Fun Campus Online
Proposal No. FP/HP/Others/142897/2021.

MUCKMANAGEMENTPLAN (MMP).

Sr.	Description	Quantity
1	Total Quantity of Muck being produced	70.00cum
2	Deduction for useful stone as required under the clause of agreement to be executed by the Contractor and Executive Engineer of Project 0.4867 ha.	23.33
3	Net Balance Quantity of Debries /Muck(1-2)	46.67
4	Quantity available on site with swell factor @ 40%	18.66
	Total(sr.3+4)	65.33cum(B)
5	Material/Muck to be used in Project:-	
(i)	Deduction of material required for the construction of dumping place in dry masonry wall/Edge wall/RwallandBwall@45%	29.39
(ii)	Less for material/Muck required for leveling of the proposed site for the Construction @20%	13.33
(iii)	Less for material/Muck required for the construction of the proposed site on the Analogy of half cutting half filling @35%	22.86
	Total:-(i)+(ii)+(iii)	65.33 cum(C)
6	Net material/Muck to dumped in dumping Point(B-C) in Cum	0.00

C/s
D.F.O. Theog

For Kufri Fun Campus Pvt. Ltd.

Baldev Singh Thakur
Director/ Proprietor.
Kufri Fun Campus.
Shimla HP.