

**General abstract of cost for Improvement and Augmentation of W.S.S.  
Thaplal in Tehsil Ramnagar District Udhampur**

Particulars	Amount
Cost for the construction of 01 nos of Inlet tank at source	0.59
Cost for construction of cut off wall at nallah source at Satyan	2.25
Cost for the construction of 01 nos. Sedimentation Tanks near source	1.05
Cost for the construction of 5,000 Gallons Slow Sand Filtration Plant at vill Thaplal.	7.78
Cost for the construction of Chokidar cum operator Quarter at village Thaplal	7.00
Cost for construction of 30,000 Gallons Service Reservoir 01 Nos at village Thaplal.	9.04
Cost for the construction of tapping source water through V- Screen pipe 02 nos @ Rs 10,000/- each	0.39
Cost for construction of 06Nos steel Rope crossing at different place	9.47
Cost for the construction of Valve Pit 02 Nos	0.43
Cost for construction of public stand posts 88 Nos	2.72
Cost for the construction of Chain Link Fencing around the civil structures 02 place at different site	2.84
Provision for Survey and investigation Work 50 Km	0.98
Cost for Improvement of existing system of various dia G.I. Pipes	4.69
Improvement/ extension/up gradation of existing system and laying and fitting of G.I.Pipes Pipes i.e. Gravity Main and Distribution System 50700 mtrs ( Estimate Enclosed) for coverage of NC/PC / un-register (Leftout) habitations including labour and material components	249.04
Cost for construction of dry wall for strenthning the gravity main	20.07
Provision for forest land compensation during execution of work under forest land	4.50 5.19
Provision for Land Compensation for new structures 02 Kanal @ Rs 1.50 Lacs/kanal	6.00
Total	325.76
Add 2.5 % for work charge contingencies except item no 15 and 16	7.95
Grand.Total	333.71

Say Rs 333.71 Lacs

*[Signature]*  
Junior Engineer

*[Signature]*  
Assistant Engineer  
P.H.E Sub-Division  
Ramnagar

*[Signature]*  
Assistant Executive Engineer  
P.H.E Sub-Division  
Ramnagar

*[Signature]*  
Executive Engineer  
P.H.E Division  
Udhampur