

Proposal Seeking Clearance for Electrification of
Thenmalai habitation in Sirumalai Panchayat, Dindigul Taluk in Dindigul District

ANNEXURE XI

BRIEF NOTE ON THE PROJECT

- 1) Name of Work: Erection of 22KV HT overhead line to a distance of 2.812kms through Revenue and Private land and Erection of 22KV UG cable to a distance of 3.010 kms through Forest land from Agastiyarpuram to Thenmalai in Sirumalai Panchayat and erection of one number 100KVA/22KV Distribution Transformer at Thenmalai habitation.
- 2) Name of Scheme: For effecting 1 No OHT SC to a load of 5HP at Thenmalai Habitation in Sirumalai Village to meet the drinking water requirement which is a basic amenity.
- 3) Necessity :

At Sirumalai Panchayat Thenmalai Ponnuruki are unelectrified habitations. About 1500 people are living in these habitation .Scheduled Tribal, Hindu- Paliyur people are living in there habitation.

The above people have requested Electric supply to 1 No Over Head Tank service to meet drinking water requirements for the above people. The president Sirumalai Panchayat has applied for the scheme and estimate has been Sanctioned by Chief Engineer / Distribution / Madurai Region Vide No : **(per)(CMD) TANGEDCO Proceedings NO 313, dated 28.7.2015 at a cost of Rs.58,34,390/-**.The above scheme will meet the drinking water requirement which is a essential basic amenity .Also electric supply to in and around there habitation can be extended for houses and street lights and the people living in there habitation will be benefited. The sirumalai Panchayat has passed a resolution in this regard.


Hence the above scheme will meet the basic amenity requirements and also will help in development for the people.

PROJECT DETAILS

As per BP (per (CMD)TANGEDCO proceeding no 313 date 28.07.15

1. Erection of 22 KV HT 3 Wire line for a length of 2.812Km from sirumalai Agasthiyarpuram to Thenmalai in Sirumalai
2. Laying of 22KV 3X50SQmm cable to a distance of 3.010Km (land belongs to forest department)
3. Erection of 1 No 22 KV / 100 KVA Distribution Transformer Structure.
5. Erection of 1no DP structure.
4. Erection of LT 3 Phase 4 Wire LT line to a length of 0.035 Km
5. Erection of 1 No Over Head Tank service to a load of 5 HP.

Date.


Executive Engineer
TNEB
South Dindigul.