

HIMACHAL FUTURISTIC COMMUNICATIONS LTD.

C-135, Industrial Area, Phase VIII, Mohali
Punjab, Mohali-160055, PUNJAB, INDIA
Telephone : 0091-0172 -0172-4922380/01724922205
Email: Vineet.kalra@ril.com

**WORK ORDER**

To 3208129 V&A VENTURES 804, 8TH FLOOR, NIRMAL TOWER 26 BARAKHAMBHA ROAD NEW DELHI DELHI Pin Code: 110001 INDIA Phone : +919999974636 Fax : E-Mail : AMIT.CHAUDHARY@VAVENTURES.CO.IN Attention : AJAY	Work Order No. : 169/13033049 Date : 02.08.2019 GSTN Of Biller : 03AAMFV5895L1ZD Bill From State : Punjab Bill From : 5133166 Contractor's Quot. Ref : Date : Our Ref :
--	--

In accepting this WORK ORDER, CONTRACTOR agrees to furnish the GOODS/Do WORK specified in full accordance with all conditions set forth herein and / or attachments hereto. All drawings, designs, specifications and other data prepared by OWNER and related thereto are the property of the OWNER and must be returned to OWNER upon completion by CONTRACTOR of the obligations under this WORK ORDER. The information contained herein is not to be released or disclosed for any other use or purpose other than for the execution of this WORK ORDER.

It is important that CONTRACTOR signs and returns the Work Order copy within three (3) days of receipt.

No other form of Order acceptance will be accepted. Failure to return the Order acceptance does not diminish the responsibilities as set forth herein, but may result in delay to any payment(s) that may be due and may be the cause for termination of this WORK ORDER.

For all correspondence, Please quote Contract/Work Order No.

For detailed commercial terms & conditions, please refer line items terms/enclosures.

WO Period From DT : 02.08.2019 To DT : 31.10.2019	Value of Work CGST SGST	INR INR INR	3,402,000.00 306,180.00 306,180.00			
TOTAL ORDER VALUE		INR	4,014,360.00			
Value in Words :(Rs. Forty Lakh Fourteen Thousand Three Hundred Sixty only) For other details, please refer line items.						
Delivery Terms : N/A punjab Engineer in Charge : MR. ANIL WADHWA						
Payment Terms : See Page Inside						
P&C Head - Manoj K Goel FC&A Head - Yash Mittal Yash Mittal SCH/CMM/MKT - Gurinder Singh Kalra	for HIMACHAL FUTURISTIC COMMUNICATIONS LTD. This is computer generated print Signature not required	CONTRACTOR'S Acceptance <table><tr><td>Signature</td><td>Title</td><td>Date</td></tr></table>		Signature	Title	Date
Signature	Title	Date				

REGISTERED OFFICE : 8, ELECTRONICS COMPLEX, CHAMBAGHAT, SOLAN -173213



PURCHASE ORDER

Number 169/13033049 Dt.02.08.2019

Page No: 1

No	Item Code	Material/Work Description	Quantity	UOM	Price Details	Unit Rate	Amount (INR)
1		Jalandhar_Subhanpur_MainSpan	1	PU	Value of Work		
					CGST	9.00 %	3,078,000.00
					SGST	9.00 %	277,020.00
		Service Accounting Number:	998734				

The item covers the following Work :

10 3318596 LAY OFC-2 DUCTS BY OPEN CUT/HDD-NFIM 19,000M - Meter
Net value of item 162.00 3,078,000.00
INSTALLATION OF 2 NOS 40MM OD HDPE DUCTS BY OPEN CUT /HDD METHOD IN ALL TYPES OF SOIL /MURRUM /HARD ROCK OR ANY OTHER STRATA INCLUDING INSTALLATION OF MH/HH, DIT OF 2 DUCTS , BLOWING , SPLICING , TERMINATION & LINK TESTING OF 1 NO 48 FIBRE LOOSE TUBE OFC THROUGH ONE OF THE DUCTS INCLUDING BUT NOT LIMITED TO, SUPPLIES AND INSTALLATION OF MATERIALS SUCH AS WARNING TAPE ; RCC PROTECTIONS SLABS 500 MM X 300 MM X 40MM/ RED STONE 25 MM THICK X 300 MM WIDTH X 500 MM LENGTH ; GI / DWC PIPE OF SIZE SUITABLE FOR INSTALLATION OF SPECIFIED NUMBER OF DUCTS ; CONCRETE MATERIALS FOR PLACING PCC/RCC AT MH AND OTHER LOCATIONS ; CLAMPING & COUPLING MATERIALS FOR DWC PIPE OR GI PIPE, OF SIZE SUITABLE ETC. ; DUCT COUPLERS, END PLUGS, SIMPLEX PLUGS ETC. ; EARTHING MATERIALS ;TAGGING MATERIALS.ANY OTHER MATERIAL AS MAY BE REQUIRED AS PER CONSTRUCTION SPECIFICATIONS.#

Released from the line 60

2		Jalandhar_Subhanpur_LM	1	PU	Value of Work		
		List of LM Sites falling on the span are:-			CGST	9.00 %	324,000.00
		I-PB-KPRL-ENB-6015			SGST	9.00 %	29,160.00
		I-PB-JLDB-ENB-I010					29,160.00
		Service Accounting Number:	998734				

The item covers the following Work :

10 3318597 LAY OFC-2 DUCTS BY OPEN CUT/HDD INC.NFIM 2,000 M - Meter
Net value of item 162.00 324,000.00
INSTALLATION OF 2 NOS 40MM OD HDPE DUCTS BY OPEN CUT /HDD METHOD IN ALL TYPES OF SOIL /MURRUM /HARD ROCK OR ANY OTHER STRATA INCLUDING INSTALLATION OF MH/HH, DIT OF 2 DUCTS , BLOWING , SPLICING , TERMINATION & LINK TESTING OF 1 NO 24 FIBRE LOOSE TUBE OFC THROUGH ONE OF THE DUCTS INCLUDING BUT NOT LIMITED TO, SUPPLIES AND INSTALLATION OF MATERIALS SUCH AS WARNING TAPE ; RCC PROTECTIONS SLABS 500 MM X 300 MM X 40MM/ RED STONE 25 MM THICK X 300 MM WIDTH X 500 MM LENGTH ; GI / DWC PIPE OF SIZE SUITABLE FOR INSTALLATION OF SPECIFIED NUMBER OF DUCTS ; CONCRETE MATERIALS FOR PLACING PCC/RCC AT MH AND OTHER LOCATIONS ; CLAMPING & COUPLING MATERIALS FOR DWC PIPE OR GI PIPE, OF SIZE SUITABLE ETC. ; DUCT COUPLERS, END PLUGS, SIMPLEX PLUGS ETC ; EARTHING MATERIALS ;TAGGING MATERIALS.ANY OTHER MATERIAL AS MAY BE REQUIRED AS PER CONSTRUCTION SPECIFICATIONS.#

Released from the line 100



PURCHASE ORDER

Number 169/13033049 Dt.02.08.2019

Page No: 2

Total Value of Work	INR	3,402,000.00
Total CGST	INR	306,180.00
Total SGST	INR	306,180.00

Total Order Value:	INR	4,014,360.00
--------------------	-----	--------------

Terms of payment :

Payment Terms as per agreement No :-3208129/PUNJAB/NLD/2016/NOVEMBER

&

Addendum to agreement dated-06 July,2017

Vendor Bank Details:

Bank Account No. :

Bank Name :

City :

Guarantees / Warranties :

Execution Partners must ensure following:

1. Assess the work place with respect to probable electrical hazard and necessary precaution to be taken to prevent electrocution, as per Indian electricity act & rules.
2. Strict compliance of use of Personal Protection Equipment (PPE) by all the workers / supervisors (full body harness, safety shoes, jackets, helmets, hand gloves, face shield, gum boots, etc.).
3. Always practice to draw power using 3-pin switch / socket for all power tools without any joints in power cables.
4. Installation of hard barricades surrounding the erection / material lifting area with adequate warning boards to restrict the unauthorized entry.
5. Always use insulated tools & tackles with proper grounding of the power distribution boards.
6. Proper illumination and lighting arrangement for working in darkness.
7. Deputation of trained & experienced supervisor at work place.
8. Ensure to discharge the HT power line after confirmation of disconnection from local authorities in case of shut down, before starting of work.
9. Work permit system to be strictly implemented as per applicability treating all electrical cables / conductors as live unless tested otherwise.
10. Strict use of non-conductive ladders, calibrated as well as insulated tools & tackles.
11. Emergency contact numbers and fully equipped first aid box must be easily accessible at work site.
12. Awareness of HSEF guidelines and SOP's is very much required to be created among workers during tool box talks at site.
13. Any accident which takes place due to lapses or negligence on the part of the vendor, must be dealt with severely. Fatal accident will be treated as an offence and will warrant suitable punitive action to the extent of black-listing of the vendor.
14. Always maintain specified minimum separation, as mentioned below from overhead or exposed power lines while working:
Voltage LT power Up to 440 V 440 V to 11 KV 11 KV to 22 KV 22 kV to 66 KV
Ordinary Person 1.2 m 3 m 3 m 3 m
Authorized Person 0.7 m 0.7 m 0.7 m 1 m

Contract riders (clauses) :

Recovery Clause and Mark-up Percentage (To be incorporated in WOs as per above guidelines)

In the event Contractor consumes any of Free Issue Material (FIM) issued to them in excess of that required to execute the works including permissible wastage allowances and tolerances, Company shall recover 125% of the landed cost (25% mark-up) of the said FIM from Contractor. The landed



PURCHASE ORDER

Number 169/13033049 Dt.02.08.2019

Page No: 3

cost shall include the latest price for said material, along with all the levies, duties, taxes, transportation, etc. and shall be calculated as per Company policy notified from time to time.

Engineer-In-charge :

MR. ANIL WADHWA

Other contractual stipulations :

Address-Bill to party and bill submission:

HIMACHAL FUTURISTIC COMMUNICATIONS LIMITED

Paarth 802, Plot No. GH-66

Sector - 55

Gurgaon, Haryana

Terms of Advance :

P.O. Line : 00001

Mile Stone Description	-	% of Payment
------------------------	---	--------------

PAYMENT TO BE DONE UPON COMPLETION OF ROUTE, LM AN	-	100
--	---	-----

P.O. Line : 00002

Mile Stone Description	-	% of Payment
------------------------	---	--------------

PAYMENT TO BE DONE UPON COMPLETION OF ROUTE, LM AN	-	100
--	---	-----

Note(S): 1. It is essential that the Contractor shall mention ItemNo. & Item code along with corresponding Material/Work Description and W.O.No. as mentioned above, in the Delivery challan (On-Shore Order), Measurement sheet and invoice for ease of material Inwarding, Certification of work and Bill Processing. Failure to do so may be the grounds for the rejections(s) or delay in release of payment(s).

PLANT REGISTRATION NO. : 03AAACH4041D1ZE



PURCHASE ORDER

Number : 169/13033049

Date 02.08.2019

HIMACHAL FUTURISTIC COMMUNICATIONS LTD.

All Detailed T&C will be as per agreement No
:-3208129/PUNJAB/NLD/2016/NOVEMBER

&

Addendum to agreement dated-06 July,2017

and

E-Bidding (Reverse Auction) Term sheet for NLD route allocation.