


Name of Work : - Construction of Manaldhura to Nanankote Motor Road under PMGSY

Quantity of R/Wall for Debries Disposal.

Location of dumping yard	No.	Length	Width	Height	Quantity	Unit	Rate	Amount
Km-1	1x1	60.00	1.50	7.50	675.00	Cum	1146.30	773752.5
Km-1	1x1	7.50	1.50	7.50	84.38	Cum	1146.30	96719.0625
Km-2	1x1	20.00	1.50	7.50	225.00	Cum	1146.30	257917.5
Km-2	1x1	7.00	1.50	7.50	78.75	Cum	1146.30	90271.125
Km-3	1x1	48.00	1.50	7.50	540.00	Cum	1146.30	619002
Km-3	1x1	35.00	1.50	7.50	393.75	Cum	1146.30	451355.625
					1996.88			1515265.31
							Total	1515265.31

Cost of cartage Muck Disposal in dumping yard.

S.No	Quantity	Rate	Amount
1	11854.05	45.00	533432.03
Total			533432.03


J.E.
Constt. Div.
PWD Salt


A.E.
Constt. Div.
Div.
PWD Salt

E.E.
Constt. Div.
PWD Salt

Location and Quantity of Debries Disposal

Location of dumping yard	No.	Length	Width	Height	Type of Land	Quantity
Km-1	1x1	60.25	10.41	7.50	Civil/Vanpanchayat land	4704.02
Km-1	1x1	7.50	10.45	7.50	Civil/Vanpanchayat land	587.81
Km-2	1x1	21.00	9.80	7.50	Civil/Vanpanchayat land	1543.50
Km-2	1x1	7.50	10.45	7.50	Civil/Vanpanchayat land	587.81
Km-3	1x1	48.00	10.20	7.50	Civil/Vanpanchayat land	3672.00
Km-3	1x1	48.00	10.39	7.50	Civil/Vanpanchayat land	3740.40
						14835.54

Pradeep
J.F.

Name of Work : - Construction of Manaldhura to Nanankote Motor Under PMGSY

Sl. No.	Description	Qty.	Unit	Remark
1	Material Received from hill side cutting in $\frac{1}{2}$ (3000x3x3)	13500.00	Cum	
	40% for swelling factor	5400.00	Cum	
	Total	18900.00	Cum	

use of material

Sl. No.	Description	Qty.	Unit
1	R.R. Stone masonry laid 1:5	448.24	Cum
2	R.R. Stone masonry laid in dry	1239.08	Cum
3	Hand packed stone filling	198.33	Cum
4	Construction of wire create	450.00	Cum
5	Construction of parapet.	282.24	Cum
6	Scupper 1:5 & dry	866.88	Cum
7	Collie wall	169.50	Cum
9	Granular sub base/base/surface	1394.81	Cum
	Total used	5049.08	Cum
	Total use in dumping Zone	1996.88	
	Total	7045.96	Cum
10	Material disposal in cartage in dumping yard	11854.05	Cum


J.E.
Constt. Div. PWD
Salt


A.E.
Constt. Div. PWD
Salt

E.E.
Constt. Div. PWD
Salt

Summary Cost of Muck Disposal.

Name of Work : - Construction of Manaldhura to Nanankote Motor
Road under PMGSY

S.No.	Description	Amount
1	Compensation of Land for Muck Disposal.	0.00
2	Construction of R/Wall for dumping yards.	1515265.31
3	Cost of cartage for debries disposal in dumping yards.	533432.03
Total		2048697.34
Say Rs.		2048697.34


A.E.

Constt. Div. PWD Salt

E.E.

Constt. Div. PWD Salt