

BOARD SIDE LT POLE SCHEDULE													
Location	Spen Length	Psc Pole 8.0 mtr	Base Plate	LT 3 Ph. X arm	Back Clamp 8.0Mtr	LT Shackie W MP	LT Pin Insulator	Aluminium Knob	Stay set Complate	Bolt & Nut.	Earthing	Concrting	AAAC 7/2.50 for LT
L1	40	1	1	1	1	0		1	1	1	1	1	160
L2	55	1	1	1	1		3	1		1	1	1	220
L3	55	1	1	1	1		3	1		1	1	1	220
L4	55	1	1	1	1		3	1		1	1	1	220
L5	55	1	1	1	1		3	1		1	1	1	220
L6	50			1	1	3		1	1	1	1	1	220
SS				2	2	6	6	2		1			200
L7	20	1	1	2	2	6		2	1	1	1	1	80
L8	40	1	1	1	1		3	1	1	1	1	1	160
L9	50	1	1	2	2	6		2	1	1	1	1	200
L10	30	1	1	1	1		3	1	1	1	1	1	120
L11	50	1	1	1	1		3	1		1	1	1	200
L12	50	1	1	1	1		3	1	1	1	1	1	200
L13	50	1	1	2	2	6		2	1	1	1	1	200
L14	45	1	1	1	1		3	1	1	1	1	1	180
L15	45	1	1	1	1		3	1	1	1	1	1	180
L16	40	1	1	2	2	6		2	1	1	1	1	160
L17	40	1	1	1	1		3	1	1	1	1	1	160
L18	40	1	1	1	1		3	1	1	1	1	1	160
L19	10												40
D15-16						14							40
S Total													3280
Sagging Jumber 5%													
Total	820	17	17	24	24	53	42	24	13	19	17	17	3444
Party Side LT Pole Shedule													
L20	50	1	1	1	1		3	1		1	1	1	200
L21	35	1	1	1	1	3		1	1	1	1	1	140
S.Total													340
Sagging Jumber 5%													
Total	85	2	2	2	2	3	3	2	1	2	2	2	357
overall	905	19	19	26	26	56	45	26	14	21	19	19	3801

Forwarded: By Order  
  
AEE/PRO&DEV/Dindigul

Sd.xxx  
Superintending Engineer,  
DEDC/Dindigul.