


## Material Recived From Hill Side Cutting

Name of Work : Chaplodi to Kulyani Motor Road

Block : Pabo

District : PAURI

S No	Item /Description	Unit	Quantity	Remark
1	2	3	4	5
1	Soft Soil	Cum	117431.00	
2	Ordinary Rock	Cum	68406.00	
3	Hard Rock	Cum	23948.00	
Material Received From Hill Cuting			<b>209785.00</b>	Cum

  
Shah  
20

  
Assistant Engineer III  
PMGSY  
Irrigation Division  
Srinagar, Garhwal

  
Executive Engineer  
PMGSY Irrigation Division  
Srinagar Garhwal

## Use of Material


**Name of Work : Chaplodi to Kulyani Motor Road**

**Block : Pabo**

**District : PAURI**

<b>Sno</b>	<b>Description</b>	<b>Unit</b>	<b>Qty</b>
1	2	3	4
1	Construction Of Super Elevation	Cum	30834.00
2	Construction Of Coolie Wall	Cum	3051.28
3	Patri Filling	Cum	7280.25
4	Wall RR-Dry Stone Masonary	Cum	5667.55
5	Wall RR-1:5 Stone Masonary	Cum	5963.66
6	Hand Packed Stone Filling	Cum	4603.03
7	Edge Stone rode Side	Cum	5935.00
8	Back Cutting Pillar	Cum	100.00
9	Parapet wall road Side	Cum	12000.00
10	Wire crate road protection	Cum	1946.26
11	Pucca Drain Along road	Cum	-
12	GSB- Sub Base Coarse	Cum	7771.93
13	G-III Base Corse	Cum	8685.82
14	Cd-Work (Scupper)	Cum	-
15	PCC work	Cum	938.84
16	Utility and other Misc	Cum	50000.00
	<b>Use of Material</b>	<b>Cum</b>	<b>144777.62</b>

  
23

  
Assistant Engineer III  
PMOSY  
Irrigation Division  
Srinagar, Garhwal

  
Executive Engineer  
PMGSY Irrigation Division  
Srinagar Garhwal

## Balance Material For Dumping Zone

**Name of Work : Chaplodi to Kulyani Motor Road ( Stage -I&II) Motor**

**Block : Pabo**

**District : PAURI**

<b>Sno</b>	<b>Description</b>	<b>Unit</b>	<b>Qty</b>
<b>1</b>	<b>2</b>	<b>3</b>	<b>4</b>
1	Material Recived From Hill Side Cutting	Cum	209785.00
2	Use Of Material for Construction	Cum	144777.62
3	Balance Material For Dumping Zone	Cum	65007.38
<b>Total Material to be Dump in Dumping Zone</b>		<b>Cum</b>	<b>65007.38</b>

*Handwritten signature and date: 20/10/16*

*Handwritten signature*  
Assistant Engineer III  
PMGSY  
Irrigation Division  
Srinagar, Garhwal

*Handwritten signature*  
Executive Engineer  
PMGSY Irrigation Division  
Srinagar Garhwal

## Capacities of Dumping Zone


Name of Work : Chaplodi to Kulyani Motor Road ( Stage -I & II)

**Block : Pabo**

**District : PAURI**

Sno	Size Of Dumpi		Type of Land			Capacity Of Dumping Yard	
	Area = (Length X Width)		Sqm	Area		Height	Cum
1	55.00	45.50	2502.5	Nap Land (Private)	2502.50	7.00	17517.50
2	60.00	25.40	1524	Nap Land (Private)	1524.00	7.00	10668.00
3	50.00	20.00	1000	Nap Land (Private)	1000.00	7.00	7000.00
4	50.00	25.00	1250	Nap Land (Private)	1250.00	7.00	8750.00
5	49.30	35.50	1750.15	Nap Land (Private)	1750.15	7.00	12251.05
6	40.00	31.50	1260	Nap Land (Private)	1260.00	7.00	8820.00
			9286.65				65006.55



  
Assistant Engineer III  
PMGSY  
Irrigation Division  
Srinagar, Garhwal

  
Executive Engineer  
PMGSY Irrigation Division  
Srinagar Garhwal

**DUMPING ZONE LOCATION.**

**Name of Work : Chaplodi to Kulyani Motor Road ( Stage -I&II)**

**Block : Pabo**

**District : PAURI**

S No	KM	X-SECTION	NORTHING	EASTING	LAND TYPE	VILLAGE
1	KM-01	X/s-0/25-0/28	30-5-40.83	78-57-7.18	NAAP LAND	Mankoli
2	KM-01	X/s-0/36-0/38	30-5-47.04	78-57-9.94	NAAP LAND	Mankoli
3	KM-07	X/s-6/3-6/6	30-5-44.66	78-57-54.61	NAAP LAND	Faldari
4	KM-07	X/s-6/10-7/13	30-5-42.98	78-58-1.56	NAAP LAND	Faldari
5	KM-09	X/s-8/5-8/7	30-5-22.22	78-58-28.55	NAAP LAND	Ghumki
6	KM-014	X/s-14/09-14/11	30-5-16.83	78-59-13.71	NAAP LAND	Kulyani

*Shah*  
JS

*SA*  
Assistant Engineer III  
PMGSY  
Irrigation Division  
Srinagar, Garhwal

*BS*  
Executive Engineer  
PMGSY Irrigation Division  
Srinagar Garhwal