

BharatNet Project Survey Report (Phase- II)

Block		Nawanshahr		State		Punjab				
5. Cable Laying details and ROW informations for the proposed route										
SI No	Panchayat Name	Type of soil and length(Optional)			Estimated HDD length (in meters)	Estimated Open Trench (in meters)	Road Crossings length	Bridge/ Nala/ Culverts crossings length (mts)	FOREST (Y/N)	
		Kachcha	Pacca	Rocky						
1	ALACHAUR	3901.50			3891.50		10.00		Y	
2	MALPUR ARKAN	4276.86			4256.86		20.00		Y	
3	BHANGAL KALAN	1882.92			1802.92		45.00	35	Y	
4	BEGAMPUR	3591.42			3571.42		20.00		Y	
5	JAFARPUR(D)	1534.08			1514.08		20.00		Y	
6	BAIRSIAN	2466.36			2441.36		25.00		Y	
7	GARHI FATEH KHAN	19492.20			19467.20		25.00		Y	
8	NILOWAL	3468.00			3448.00		20.00		Y	
9	SAIDPUR KALAN	4405.38			4390.38		15.00		Y	
10	KANAUN	435.54			390.54		45.00		Y	
11	NAI MAZARA	3473.10			3423.10		20.00	30	Y	
12	SANAWA	1368.84			1318.84		20.00	30	Y	
13	SAJAWALPUR	733.38			718.38		15.00		Y	
14	RAMGARH	4113.66			4093.66		20.00		Y	
15	USMANPUR	1282.14			1262.14		20.00		Y	
16	SOETA	1328.04			1283.04		45.00		Y	
17	SEHBAJPUR	1878.84			1833.84		45.00		Y	
18	MAZARA KALAN	3732.18			3712.18		20.00		Y	
19	MAZARA KHURD	498.78			473.78		25.00		Y	
20	MAJHOOR	5077.56			5047.56		30.00		Y	
21	BIROWAL	2276.64			2256.64		20.00		Y	
22	UTTAL	1434.12			1414.12		20.00		Y	
23	OLT TO OLT	23416.34			23396.34		20.00		Y	
Total		96067.88	0.00	0.00	95407.88	0.00	565.00	95.00		

VTL REP

TPA REP

BBNL REP



ABHAY KORI
Assistant Manager (S&T)
RITES LIMITED
(A Govt. of India Enterprise)

Assistant Manager
BBNL PUNJAB-CHANDIGARH