


KERALA STATE ELECTRICITY BOARD LIMITED

ESTIMATE REPORT

Name of work: Interlinking 100 KVA Korenchira Tr with 100 KVA TK Polimers Tr
Estimate Amount: Rs.1522373/- (Rupees Fifteen lakh Twenty Two Thousand Three Hundred and Seventy Three only)

An estimate is proposed for interlinking two transformers, 100 KVA Korenchira and 400 KVA TK Polimers transformer at Oorokkad area. Both the transformers are connected at far end of two different branch line from 11 KV Karumathra feeder and at present there is no back feeding facility for this two transformers. 400 KVA TK Polimers transformer is for an HT consumer. For providing back feeding facility it is necessary to draw 920 metre 11 KV line between the two transformers and available route for drawing the line is through forest area, hence 11 KV ABC line is proposed. Beneficiaries of this work is about 250 consumers including one HT consumer. This work is proposed under system improvement scheme.


ASSISTANT ENGINEER
ELECTRICAL SECTION
K S E B Ltd.
PUNNAMPARAMBU