

परियोजना का नाम :- जनपद चमोली में पी0एम0जी0एस0वाई0 के अन्तर्गत बगोली - चूला मोटर मार्ग निर्माण हेतु 2.118 हे०
सिविल भूमि का ग्राम्य विकास विभाग को हस्तान्तरण प्रस्ताव।

परियोजना के सीमांकन पीलरों का नव निर्माण
मोटर मार्ग की कुल ल०
सीमांकन पीलरों की सं०

7.275 किमी

73 न०

क्र० सं०	कार्य का विवरण	सं०	नपत मीटरों में			मात्रा घनमी०	दर रु०	घनराशि रु०
			ल०	चौ०	ऊँ०			
1	2	3	4	5	6	7	8	9
a	मिट्टी पत्थर कटान कार्य							
	स्थल विकास कार्य (मि०प०)	73 x 1	1.00	1.00	(1+0) / 2	36.500000		
	सीमा पीलरों के निर्माण हेतु बुनियाद खुदाई कार्य	73 x 1	1.00	1.00	0.30	21.900000		
	योग (मि०प०)					58.400000	226.40	13221.76
b	आधार में कोयला विछाना	73 No.				103	LS	5150.00
c	बैस में आर०सी०सी० स्लैप डालना	73 x 1	1.00	1.00	0.10	7.300000		
	उक्त स्लैप के मध्य में आर०सी०सी० पीलर निर्माण	73 x 1	0.30	0.30	1.10	7.227000		
	योग (आर०सी०सी० कार्य का)					14.527000	8325.50	120944.54
d	सीमेंट प्लास्टर करना । 1:4 सी०एस० 12एम०एम० में							
	खड्डे भाग में	73 x 4	0.30		1.10	96.360000		
	टोप में	73 x 1	0.30	0.30		6.570000		
	योग(1:4 प्लास्टर कार्य)					102.930000	167.90	17281.95
e	सफेदी कार्य करना					102.930000	18.30	1883.62
f	आर०सी०सी० में सरिया की मात्रा	14.52700 Cum	x (0.785x1.5x100) kg/ cum=			1710.55425	64.30	109988.64
						kg	Rs / kg	
					योग			268470.50

प्रस्तावित प्राकलन की राशि रु० 268471

Public Works Department Uttarakhand DSR REPORT
Name Bilding / Roads & Bridges Uttarakhand
Rate Card Block 12 Narain Bagar (CHAMOLI) Effective Date 16/05/2014
Year 2014-2015

S.No	Description	Rate	Item No.	Unit
1	2	3	4	5
1	Excavation in all kinds of soil	226.40	80971 1-2-6-1	Cum.
2	12 mm cement plaster of mix 1:4(1 cement : 4 fine sand)	167.90	81957 1-13-1-1	Cum.
3	Reinforced cement concrete work in walls (any thickness), including attached pilaste shuttering, finishing and reinforcement		1--5-2	
	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	8,325.50	81118 1--5-2-3	cu.m
4	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete.		1-5-22	
	Reinforcement for R.C.C. Work Using Mild Steel and Medium /Tensile Steel Bars	64.30	81164 1-5-22-1	kilogram
5	New work (two or more coats) with a base coat of white washing with lime	18.30	82015 1-13-38-1	Cum.

वन क्षेत्राधिकारी
असेंडेंट इंजीनियर रंज
नारायणबाग

म.प.
(सिद्धपाल सिंह) 9858

प्रभागीय DPO अधिकारी
बदोलाय वन विभाग
बोरेखण्ड (चमोली)