

MAHARASHTRA STATE ELECTRICITY TRANSMISSION CO. LTD.
132 KV LAKHANDUR TO MORGAON (ARJUN) TRANSMISSION LINE TOWER SCHEDULE

Sr No	AP No	Tower Type	Wt. Span (Hot)			Adjacent Span			Crossing / Remark
			Left	Right	Total	Left	Right	Total	
	C1-EX TWR	DDE+0	0.00	11.03	11	0.00	79.13	79	
1	C1-1/0	D + 0	68.1	74.75	143	79.13	70.8	150	
2	C1-H1	SD	-3.95	0.36	-4	70.8	65.17	136	
3	C1-H2	SD	64.81	55.64	120	65.17	109.87	175	
4	2/0	D + 0	54.23	182.16	236	109.87	298.07	408	
	C2 EX.TWR.1	DDE + 0	0.00	76.22	76	0.00	145.22	145	
	C2 EX.TWR.2	DD+0	68.99	53.04	122	145.22	28.06	173	
	2/0	D+0	-24.98	182.16	157	28.06	298.07	326	
5	3/0	D+0	115.91	167.79	284	298.07	310.93	609	Canal, Cart track
6	3/1	A+0	143.14	132.16	275	310.93	255.34	566	Cart track
7	4/0	C+0	123.19	164.94	288	255.34	325	580	
8	4/1	A+0	140.06	130.32	270	325	276.57	602	Cart track
9	5/0	B + 3	166.26	151.97	318	276.57	324.63	601	Cart track, Nala, LT Line
10	6/0	B+6	172.66	178.78	351	324.63	295.96	621	underground water pipe line, 11 kv Power line SH
11	7/02	D+0	117.18	132.36	250	295.96	245	541	LT Line, Cart track
12	7/1	B+0	112.64	130.06	243	245	283.98	529	
13	8/0	C+0	153.92	144.61	299	283.98	315	599	Nala
14	8/1	A+0	170.39	133.62	304	315	280	595	Cart track
15	8/2	A+0	146.38	150.94	297	280	300	580	Canal, Cart track

16	8/3	A+0	149.06	137.74	281	300	295	595	
									Cart track
17	8/4	B+0	163.26	123.53	287	295	270	565	
									Cart track, Canal, Cart track
18	8/5	B + 0	146.47	98.61	245	270	210.37	480	
									Pond, Cart track
19	9/0	D+0	111.77	105.28	217	210.37	280	490	
									11 KV Power line, Canal, Cart track
20	9/1	A+6	174.72	212.66	387	280	340	620	
21	9/2	A+0	127.34	151.72	279	340	299.65	640	
22	10/0	C+0	147.92	150.51	298	299.65	285.00	585	
									Cart track, Drain
23	10/1	A+0	134.5	169.66	304	285	345	630	
24	10/2	A+0	175.34	137.01	312	345	350	695	
									Cart track
25	10/3	A+3	212.99	149.45	362	350	247.43	597	Protected Forest
									Cart track, 11 KV Power line, Canal, Cart track
26	11/0	C+0	97.98	172.29	270	247.43	310	557	Protected Forest
									ASP Road
27	11/1	A+0	137.72	150.48	288	310	290	600	
									Drain
28	11/2	A+0	139.52	138.24	278	290	300	590	
29	11/3	A+3	161.76	171.46	333	300	340.15	640	
									Nala
30	12/0	B+0	168.69	156.36	325	340.15	328	668	
									Drain, Cart track, LT Line
31	12/1	A+0	171.64	128.99	301	328	310	638	
									Nala
32	12/2	A+0	181.01	133.71	315	310	295	605	
33	12/3	A+0	161.29	148.2	309	295	305	600	Protected Forest
34	12/4	A+0	156.8	145.86	303	305	305.38	610	
35	13/0	B+0	159.52	147.82	307	305.38	280	585	Drain, Road, Cart track, Canal 11 KV Power line
36	13/1	A+0	132.18	133.95	266	280	280	560	Restricted Forest
									Restricted Forest
37	13/2	A+0	146.05	166.83	313	280	320	600	Restricted Forest
									Restricted Forest
38	13/3	A+0	153.17	144.29	297	320	290	610	Restricted Forest

									Restricted Forest
39	13/4	A+0	145.71	156.49	302	290	315	605	Restricted Forest
									Restricted Forest
40	13/5	A+0	158.51	135.22	294	315	290	605	Restricted Forest
									Restricted Forest
41	13/6	A+0	154.78	140.51	295	290	300	590	Restricted Forest
									Nala
42	13/7	A+0	159.49	154.63	314	300	311	611	Zudpi Jungle
									Zudpi Jungle
43	13/8	B+0	156.37	123.16	280	311	300	611	Zudpi Jungle
									Zudpi Jungle
44	13/9	A+0	176.84	135.3	312	300	300	600	Zudpi Jungle
									Zudpi Jungle
45	13/10	B+0	164.7	122.17	287	300	240	540	Zudpi Jungle
									Zudpi Jungle
46	13/11	B+0	117.83	117.86	236	240	277.51	518	Zudpi Jungle
									PMGSY Road
47	14/0	D+0	159.65	143.73	303	277.51	265	543	
48	14/1	B+0	121.27	124.61	246	265	271.27	536	
49	15/0	D+0	146.67	161.54	308	271.27	285	556	
50	15/1	B+0	123.46	144.39	268	285	260	545	
									11 KV Power Line, LT Line
51	15/2	B+0	115.61	159.09	275	260	300	560	Zudpi Jungle
									ASP Road
52	15/3	A+0	140.91	144.35	285	300	302.61	603	
									Drain, Cart track, Canal, Cart track, Nala
53	16/0	D+3	158.26	178.44	337	302.61	362.42	665	
54	17/0	C+3	183.98	162.71	347	362.42	300	662	
									Cart track, Canal, 11KV Power line, LT Line.
55	17/1	A+0	137.29	138.32	276	300	300	600	
56	17/2	A+0	161.68	147.13	309	300	320	620	
57	17/3	A+0	172.87	126.23	299	320	255	575	
									Drain, ASP Road, 11 KV Power Line, Cart Track
58	17/4	A+0	128.77	151.34	280	255	285	540	
59	17/5	A+0	133.66	129.32	263	285	217.5	502	
									Cart track, Canal, cart Track, LT Line 11 KV Power Line