

TABULAR SHEET (Area Calculation) OF DFO - Obra - Land Schedule

Relicance 4G Project for Laying of Optical Fibre Cable (OFC) along with road on SH - 5 (Varanasi-Shaktinagar Road) from Km. 87.00 to 115.00, of total Km. 28.00 & 0.2901 Ha. in Social Forestry Division Obra, District: Obra - UP.

S.No	Division	Road	Owners hip of the Road	Route Name/Area	Chainage		Total Km	Total Mtrs	Total Km - (Length of Pit +Length of of Junction Box)	A	No. of Pits	Area Pit size	B	No of Junction box (1x1 Mt)	Area of Junction box	C	(A+B+C)
					From Kms.	To Kms.				Total Ha. (Lengthx0.1/1 0000)		1*1=1	Total area of Pit in			Total area of Junction box in Ha.	Total Area In Ha.
1	Obra	SH - 5	PWD	Varanasi-Shaktinagar	87.00	115.00	28.00	28000.00	27888.00	0.2789	84	84.00	0.0084	28	28.00	0.0028	0.2901
Total							28.00	28000.00	27888.00	0.2789	84	84.00	0.0084	28	28.00	0.0028	0.2901

Note:-

- 1 Size of pits = 1X1 Mts
- 2 On An Avreage 3 - 5 Pits in a KM
- 3 Size of Junction box=1x1 Mts
- 4 On An Avreage 1 Junction Box in a KM
- 5 Area of forest strip (laying of OFC)=Length x1000x0.10Mts/10000 Mts

