Alignment

Name of work-Alignment of Almora-Ghat km. 62 (Talet) to birkola Motor Road in Distt. Almora

Sanctioned Length= 10.00Km.

Sanctioned Length= 10.00Km.								
51. No.	Particular	Alignment No-1	Alignment No-2					
1	Topography	Start from Almora-Ghat km. 62 (Talet)	Start from Almora-Ghat km. 62 (Talet)					
2	Length of Road	10.00 Km.	10.00 Km.					
3	Bridging requirement No. and Length	NIL	NIL					
4	Geometric	Nap,Benap, Van Panchayat	Nap,Benap, Van Panchayat					
	(a) Gradients	1:20R 1:40R 1:24R 1:22F 1:20F 1:40F 1:24F	1:20R 1:40R 1:24R 1:22F 1:20F 1:40F 1:24F					
	(b) Curves, H.P. Bends	9 No. H.P. Bends	10 No. H.P. Bends					
5	Existing means of communication, mule path, jeep, Tracks etc.	villages are connected by foot track.	Villages are connected by foot track.					
6	Right of way, bringing out. Construction on account of built up areas, monuments and other structures	No such construction involved	Same as alignment no.1					
7	 (a) Terrain & soil condition (i) Nature of soil (ii) Geology of the area (b) Road length passing through (i) Mountainous terrain (ii) Steep terrain 	E.&B., H.S., , cultivated and Hill area Approx.30%	E.&B., H.S., , cultivated and Hill area Approx.50%					
(>	iii) Rocky stretches with indication of length in loose rocky stretches	2.00 km. Hard rock 8.00 km. ordinary rocks.	3.50 km. Hard rock 6.50 km. ordinary rocks. Nil					
	(iv) Area subject to avlanches and snow drift	Nil	Nil					
	(v) Slip Zone Area	Nil						
	(vi) Cliffs and gorges(vii) Drainage characteristics of the area including supceptibility to flooding	Nil Area has good drainges -	Nil Area has not good drainges					
	(viii) General elevation of the road indicating maximum and minimum height negotiated by main ascends and discends	maximum height 1316.87 m minimum height 1013.70 m	maximum height 1316.87 m minimum height 1013.70 m					
	(ix) Variations extants and types	Nil	Nil					

0		7	
8	Climate condition: (a) Temperature monthly max.& min. reading.	Approx.32 [°] C to 1 [°] C	Approx.32 ⁰ C to 1 ⁰ C
	(b) Rainfall data average annual peak intensities monthly distribution(to the extent	Not available	Not available
	available) I Snowfall data average annual peak intensities monthly distribution(to the extent available)	Mostly winter season Record not available	Record not available
	(d) Wind direction and velocities(e) Fog condition	Not available Often in rainy season	Not available Often in rainy season
	(f) Exposure to sun(g) Unusual weather	Almost in all the year	Almost in all the year
	conditions like cloud brust etc.	Nil	Nil
	Facilities resources (a) Landing ground (b) Dropping Zone I Food stuffs	Not available Not available Crops, vegetables, fruits, Milk production area	Not available Not available Crops, vegetables, fruits, Milk
	 (d) Labour local availability and need for import (e) Construction material (Timber, Bamboo, Sand, stone, shingle etc. extent of their availability and lead involved 	Local & Nepali labour also available Stone locally available & other material available App. 152km away at Haldwani.	production area Local & Nepali labour also available Same as alignment no.1
10	Value of land, agricultural land, Irrigated land, built up land, forest land etc.	As per current Government rate	As per current Government rate
11	Approximate Const. Cost	Total cost Rs 466.00 lacs	Total cost Rs 466.00 lacs
2	Access point indicating possibility of induction of equipment	At present access not available	Same as alignment No.1
13	Period required for construction	02 years after land transfer	Same as alignment No.1
14	Strategic Consideration	To provide better communication	Same as alignment No.1
15	Important villages, towns and markets centers to be connected	villages – Birkola & Bhaisori also Tahsil Bhanoli & district almora	Same as alignment No.1
16	Recreational potential	Good	Same as alignment No.1

17	Economic Factors: (a) Population served by the alignment	Appx. 1060	Appx. 1060
	(b) Agricultures and economic potential of the area	Population of above village will be benefited good.	Same as alignment No.1
18	Other major development projects being taken up electric projects etc.	Nil	Nil
19	 2- Misc. such as camping sites (ii) Law and other problem (iii) Royailty (iv) Availability of contractors for collection and carriage of construction material 	Nil Nil Nil Local contractor are available for the work.	Nil Nil Nil Local contractor are available for the work.
	(v) Working period available for construction of work	Approximately 6 months a year working period available	Same as alignment No.1
20	Merits	 1-Easy grades involved. 2-Min. Nap, Van Panchayat land affected from this alignment. 3- 9 No. H.P. band 	Nil
21	Demerits	Nil	1-10 No. H.P Band required . 2-Max. Nap, Van Panchayat, black cotton soil & forest land

RECOMMENDATIONS:

Alignment no.(1) recommended for approval being more economical, useful & technically feasible.

A.Assistant.Engineer C.D., P.W.D. Almora

Assistant Engineer C.D., P.W.D., Almora

Executive Engineer C.D., P.W.D., Almora