

Full Title of the Project :- CONSTRUCTION AND UPGRADATION OF BHELI LAL
DRAMAN ROAD

File No. :-


Date of Proposal :-

DETAIL OF MUCK/DEBRIES TO BE PRODUCED

Name of Work :- Construction and Upgradation of Bheli Lal Draman Road.

Detail of Quantity to be produced and used during the construction of the road .


Sr.No.	Description of Items	Quantity
1	Total Quantity to be produced during the construction	1037.74
2	To be used for soling (6.50%),wearing of road (6.50 %) and filling behind retaining walls of the road (20%) total (33%)	342
3	To be used for local use for construction of road average(total 33%)	342
4	Total Quantity to be used (2+3)	685
5	Net Quantity to be dumped (1-3)	353
6	Soil factor 30 %	106
7	G-TOTAL (5+6)	459



Assistant Executive Engineer
PWD (R&B) West Sub Division
Doda


Executive Engineer
PWD(R&B) Special Sub Division
Doda

PROFORMA -III (REFER ITEM -8)
STATEMENT SHOWING DUMPING QUANTITY OF MUCK/DEBRIS TO BE DUMPED WITH OTHER DETAIL FOR PROJECT CONSTRUCTION OF BHELL LAL DRAMAN ROAD.

S.No.	Name of Component from Muck/Debris is to be produced	Total Quantity of Muck/Debris to be produced (in Cum)	Qty.of Muck/Debris to be used locally (in Cum)	Qty.of Muck/Debris to be dumped on the compact basis (in Cum)	Factor of increase in volume for Dumping (in Cum)	Qty.of Muck/Debris to be dumped on the basis of increase (in Cum)	Name of Dumping Place	Slope of Dumping Place	Location of Dumping place and police station nearby road	Distance of Dumping place from the river	Area of dumping place with length and breadth (in hect)	Area of forest land out of land in column-10 (in hect)	Height of Muck/Debris dump expected (Vol.Area)(in mtrs.)	Remarks
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
			66%	34%										
1	Formation Cutting Work	1037.74	684.9084	352.8316	1.3	459	Koti	1H:3V	Koti, PS Beoli	10 Km	(1Nos×25×20) = 500.00 sqm or 0.05 Hect	0.11	0.92	


Assistant Executive Engineer
PWD(R&B) West Sub Division
Doda



Executive Engineer
PWD(R&B) Special Sub Division
Doda

Full Title of the Project :- CONSTRUCTION AND UPGRADATION OF ROAD FROM BHELL LAL DRAMAN ROAD.
File No. :-

Date of Proposal :-

STATEMENT SHOWING THE ROAD LINE TO BE CONSTRUCTED FROM BHELL LAL DRAMAN ROAD..

Sr.No	RD	Distance in mtr.			Width of right way	Area of Road		Total Area in Sqm	Name of Village /Muhai and Forest Area	Muck /Debries to produce Total Cum	Muck /Debries to produce locally from	Muck /Debries to produce locally for work	Remarks	
				Forest land (in mtr.)	Non Forest land (in mtr.)	Total (in mtr)								
1	4/0	19/00	100	15900	16000	6.00	Forest land (100×6.0+3×25×20) = 1100.00 Sqm or 0.11 Hect	Non Forest land 15900 × 6 = 95400.00 sqm or 9.54 Hect	9.65 Hect	Koti	1037.74	342.4542	342.4542	



Assistant Executive Engineer
PWD (R&B) West Sub Division
Doda


Executive Engineer
PWD(R&B) Special Sub Division
Doda

PERFORMA-V
STATEMENT SHOWING DETAIL OF PLACES FOR DISPOSAL OF MUCK/DEBRIS FOR THE CONSTRUCTION OF BHELL LAL
DRAMAN ROAD

Sr. No.	Name of dumping places	Location of Dumping places	Slope of Dumping place	Length & width (in mtrs.) and area of Dumping place(in Sqm)	Quantity of muck/Debris to be dumped(in 1000 cum)	Height of dumping expected	Remarks (Area in Hect)
1	1st Dumping Site, Koti	RD 8/450 to 8/475	1:3	25 x 20 = 500 sqm	459	0.918	0.05
			Total		30487		0.15

Say 0.15 Hect.


Assistant Executive Engineer
PWD(R&B) West Sub Division
Doda


Executive Engineer
PWD(R&B) Special Sub Division
Doda