

STATEMENT SHOWING COMPONENTWISE TOTAL AREA REQUIRED FOR THE CONSTRUCTION OF SHANAG MIDDLE 100KW MICRO HEP.

S.No	Name of the component	Size of component	Forest land (Sqm)	Non-Forest land (Sqm)
1	Weir Site	10x6	60.00	0
2	Feeder channel	9.5X2	19.00	0
3	Desilting tank	20x6	120.00	0
4	Flushing pipe	15x2	30.00	0
5	Dumping site-1	20x8	160.00	0
6	Dumping site-2	10x5	50.00	0
7	Dumping site-3	20x8	160.00	0
8	Dumping site-4	10x6	60.00	0
9	Penstock	363x 2	726.00	0
10	Power house	20x10	200.00	0
11	Transmission line	50x1	50.00	0
12	Tailrace	17X 2	34.00	0
Component wise total area (Sqm)			1669.00	0

Place :

Date :


SHANAG MIDDLE HEP (100KW)