

The Executive Engineer
Constn Divn No.2 PWD B&R
Hoshiarpur

To

The District Magistrate
Hoshiarpur

No

Dated:

Subject: No Objection Certificate for development of Retail outlet at Location from Garhshanker towards Nangal Distt.: Hoshiarpur.

Reference: Your office memo No457-466 LPA Dt: 03.03.2015.

In this connection it is submitted that the above site has been checked by the Sub Divn. Engineer Constn. Sub Divn. No.1 PWD B&R Garhshanker and found it is in order as per IRC hence is recommended for issuance of NOC. The land width of Road at this point should be maintained 60'-6" as per report of Revenue Department / Plan.

DA/Plan

sd/-
Executive Engineer
Constn Divn No.2 PWD B&R
Hoshiarpur


Endst No. 146-47

Dated: 23/4/15

Copy is forwarded to Sh. Rajesh Kumar, Sales Officer I.O.C Ltd., Hoshiarpur and Smt. Saruchi Devi W/O Sh. Pardeep Kumar H. No. 11323, Partap Nagar, Ward No. 25, Ludhiana.

- 1) No Construction. of any type will be erected in PWD land i.e. buffer strip , green buffer and
- 2) drain shall be out side PWD Boundary.
- 3) The surplus water will not be disposed off in PWD land.
- 4) The applicant will inform the department before taking any execution in hand.
- 5) The land width of this point will be maintained 60'-6" as per report of the revenue deptt.
- 6) The agency will obey the instruction of IRC.
- 7) The agency will obey the instruction issued by the PWD Department time to time.
- 8) During the construction, material should not be dumped/stacked on PWD land.
- 9) The agency will also followed the following instruction :
 - A Soakage pit function in a proper way as ground water recharge pits.
 - B Open drain/ slab type culverts below buffer strip is covered with iron grating on top.
 - C Slab type culvert at entry & exist over the open drain shall extend at least 0.5m beyond shoulders of driveways both on entry and exit.
 - D Level of the part of buffer strip (Green buffer) falling in PWD land shall be checked and adjusted as per site conditions so as to allow uninterrupted drainage of rainwater away from the road.
 - E The Slip road shall be separated from main road by providing road marking, solar studs or any other material as approved.

DA/ Nil


Executive Engineer
Constn Divn No.2 PWD B&R
Hoshiarpur

Endst No.

Dated:

Copy of the above is forwarded to the Sub Divisional Engineer ,Constn Sub Divn No.1 PWD B&R, Garhshanker w.r.t his letter No. 4081 Dt.: 25-03-2015 for information.