Compliance of Point 4 of Query 3

Full Title of the Project: "Laying of Railway Line for Private siding for Cement Plant.

Diversion of 7.3792 hectare area for forest land in Favour of Wonder Cement

Limited in the Revenue Village Sonu, Tehsil -Sam, Village Leela Parewar & Parewar,

Tehsil & District - Jaisalmer, Rajasthan."

Proposal No.: FP/RJ/IND/153357/2022

Date of Proposal: 11/03/2022

Area for Forest Diversion: 7.3792 Hectare

Muck Generation Report

During lying of Railway Track in the proposed diversion area, most of the area has filling while some section of chainage has cutting.

Hence the muck generated in cutting sectional area have been calculated in muck generation report. Total approx 800 M³ muck will be generated. This muck will be used in other filling sections.

However any extra muck if generated will be disposed off in approved mining dump yard. Muck disposal report & Plan already submitted to you.

Muck Generation Table

CH FROM	СН ТО	DIFFERENCE	x	Y	AVERAGE CUTTING (MTR.)	WIDTH OF CUTTING ON THIS SECTION (MTR)	VOLUME CU.MTR.
7480	7500	20	669525.821	3018842.683	0.5	10	100
7500	7520	20	669539.701	3018857.314	0.5	10	100
7520	7540	20	669553.351	3018871.702	0.5	10	100
7540	7560	20	669567.116	3018886.211	0.5	10	100
7560	7580	20	669580.881	3018900.721	0.5	10	100
7580	7600	20	669594.646	3018915.230	0.5	10	100
7600	7620	20	669608.410	3018929.740	0.5	10	100
7620	7640	20	669622.175	3018944.249	0.5	10	100
7640			669635.940	3018958.759	0.5	CHIEF IS	
		TOTAL LENGTH OF CUTTING ON THIS SECTION			= 160 MTR		
		WIDTH OF CUTTING ON THIS SECTION			= 10 MTR		
		AVERAGE DEPTH OF CUTTING			= 0.5 MTR.		
		TOTAL VOLUME			= 160x10x0.5		
					= 800 CUBIC MTR.		

Place: Jaisalmer Date: 31.5, 2022 (Rajendra Bora)
Genaral Manager (Mines)
Wonder Cement Limited
Signature of Poleciagency

Official Seal