

**ESTIMATE FOR CONSTRUCTION OF ONE CAIRN FOR FORMATION OF NH
ROAD (NH-785 EXTENSION) FROM NATHAM TO THUVARANKURICHI
THROUGH CHINNAYAMPATTI KARADU RF, NATHAM RANGE OF DINDIGUL
FOREST DIVISION, DINDIGUL.**

ABSTRACT ESTIMATE

Sl. No.	Quantity	Description	Rate	Per	Amount
1	1.00 m ²	Clearing Scrub Jungle	5.22	m ²	5.00
2	0.18 m ³	Earth work excavation and depositing on bank with initial lead of 10mt. and initial lift of 2m in HG soil SS.20B for foundation.	172.00	m ³	31.00
3	0.45 m ³	Random Rubble Masonry using HBG stone with CM 1:5	5450.00	m ³	2453.00
4	0.01 m ³	Errecting cut stone Pillar of size 0.15 x 0.15 x 0.60m	5100.00	m ³	51.00
5	2.10 m ²	White washing two coats including cost, conveyance etc.,	35.00	m ²	74.00
6	Ls	Contigencies for Numbering of RF Pillars with paint and labour charges etc.,	Ls		83.00
7	Ls	Provision for Labour Welfare Fund 1%	Ls		31.00
8	Ls	Provision for GST 12%			372.00
		Total			3100.00

(Rupees Three thousand and one hundred only)