परियोजना का नाम :- जनपद पौड़ी गढ़वाल के विधानसभा क्षेत्र चौबट्टाखाल विकास खण्ड बीरोंखाल के अन्तर्गत मोरो बैन्ड से धोबीघाट मोटर मार्ग नवनिर्माण कार्य 5.00 कि0मी0

## Performa for comparison between identified alignments

Sl. No	Variables	Alignment No-1	Alignment No-2
1	Topography	This Alignment shall be started from km 7.000 (HP Band) of Baijro jogimadhi motor road.	This Alignment shall be started from km 7.000 (HP Band) of Baijro jogimadhi motor road
2	Length of Road	5.000 km	5.500 km
3	Bridging requirement No. and Length	Nil	Nil
4	Geometric		R
	(a) Gradients	1:40 F, 1:22F, 1:20 F, 1:18F, 1:40R ,1:17R ,1:18R, 1:20 R	1:40F, 1:20F, 1:15F, 1:18R, 1:17R, 1:20R
	(b) Curves, H.P Bends	H.P bend - 0	H.P bend - 1
5	Existing Means of communication, mule path, jeep, Tracks etc.	Bridle Path	Bridle Path
6	Right of way, bringing out.	*	
7	(a) Terrain & Soil Condition.	Road passing Through mountainous Terrain and Cultivated areas	Road passing Through mountainous Terrain and Cultivated areas
	(vi) Cliffs and gorges.	Nil	Nil
	(vii) Drainage characteristics of the area including supceptibility to flooding.	Good natural drainage hence susceptibility to damage in minimum	Good natural drainage hence susceptibility to damage in minimum
	(viii) General elevation of the road indicating maximum and minimum height negotiated by main ascends and discends.	Throught Fall, Rise, Level Grade	Throught Fall, Rise, Level Grade
	(ix) Variations extants and types.	NIL	NIL
8	Climate Condition:(a) Temperature Monthly max. & min. reading.	Max.25-30°C min. 0-15°C	Max.25-30°C min. 0-15°C
	(b) Rainfall data average annual peak intensities monthly distribution (to the extent available).	Not Available	Not Available

	(c) Snowfall data average annual peak intensities monthly distribution (to the extent available).	Not Available	Not Available 28
	(d) Wind direction and velocities.	Not Available	Not Available
	(e) Fog Condition.	Some fog in winter & rainy Season	Some fog in winter & rainy Season
	(f) Exposure to sun.	Well exposure to sun	Well exposure to sun
	(g) Unusual weather condition like cloud brust etc.	NIL	NIL
9	Facilities resources.  (a) Landing ground.	NIL	NIL
	(b) Dropping Zone.	NIL	NIL
	(c) Food stuffs.	Baijro	Baijro
	(d) Labour local availability and need for import.	Local avilability & From Nepal	Local avilability & From Nepal
	(e) Construction material (Timber, Bamboo, Sand, Stone, Shingle etc. extent of their availability and lead involved.	Quarry of stone locally available and other material from Ram Nagar 10 chain head load	Quarry of stone locally available and other material from Ram Nagar 11 chain head load
10	Value of land, agricultural land, Irrigated land, bult up land, forest land etc,	As per current Cercle rate.	As per current Cercle rate.
11	Approximate Const. Cost.	259.00 Lac (approx)	284.90 Lac (approx)
12	Access point indicating possibility of induction of	Equipment will available in Ramnagar	Equipment will available in Ramnagar
	equipment.		
13	Period required for construction.	1.5 years	1.5 years
14	Strategic Consideration.	NIL	NIL
15	Important villages, towns and markets centers to be connected.	Sila malla, Sila Talla ,Diboli ,Nawasu,Pokharsain	Sila malla, Sila Talla ,Diboli ,Nawasu,Pokharsain
16	Recreational potential.	* 4	e Out

17	Economic Factors:	400	400 29
	(a) Population served by the		
	alignment.400		
	(b) Agricultures and economic potential of the area.	local villagers will be benifited to sell there crops to nearby market.	local villagers will be lesser benifited to sell there crops to nearby market.
18	other major development projects being taken up electric projects etc.	NIL	NIL
19	(i) Misc. Such as camping sites	NIL	NIL
	(ii) Law and other problem	NIL	NIL
	(iii) Royalty	NIL	NIL
	(iv) Availability of contractors for collection and carriage of construction material	Locle contractor are available for the work.	Locle contractor are available for the work.
	(v) working period available for construction of work.	12 Months	12 Months
20	Total No. of trees to be removed .	44	63
21	Average Density of forest cover	Not available	Not available
22	Total No. of Merits	1.No any irrigated cultivated land involved.     2.Alignment accepted by villagers and their elected representative.     3.Length of road is in shotter side.	NIL
23	Total No. of Demerits	NIL NIL	1. Alignment did not accepted by village & their elected representative. 2. Increasing of forest land length of road and also total length.

**RECOMMENDATIONS:-**

Alignment no. (1) Recommended for approval being more economical, useful & technically feasible.

Junior Engineer C.D. P.W.D Baijaro

Assistant Engineer C.D. P.W.D Baijaro

Executive Engineer C.D. P.W.D Baijaro

बेजरो-गढवाल

Note - Signature and approval of the concerned DFO is essential.

डा यन संरचक

पढ़वाल वन प्रभाग, पीडी