## Performa for comparison between identified alignments Page 1 of 4

Name of Work :- New Construction of Simli-Sheleshwar Motor Road in Karnprayag Constituency of District Chamoli.

SI.No Variables		Alignment No-1			Alignment No-2			
1	2	3			4			
1	Topography	Road is proposed to connect Simli- Sheleshwar road to Naini motor road via Kanot, Malla Gwad. Alignment is proposed to startfrom Km 12:00 of Simli-Sheleshwar road.			Same as Alignment No. 1.			
2	Length of Road	3.450 Km			4.000 Km			
3	Bridging requirement No. and Length	Nil			Nil			
4	Geometric							
-	(a) Gradients	1:18, 1:20, 1:24 & 1:40			1:15, 1:18 & 1:20			
51	(b) Curves, H.P Bends	04 Numbers of HP Bands			06 Numbers of HP Bands			
5	Existing Means of communication, mule path, jeep, Tracks etc.	Mule Path & Foot Tracks			Mule Path & Foot Tracks			
6	construction on account of built up	no built up area, monuments of other			out the construction work. There are			
7	Terrain & Soil Condition	(iii) The Natural Drainage characteristics of the area is good and there is no susceptibility to flooding  (iv) The elevation at the starting point of the road is 1106 m and the elevation at the end point of the road is 1376 m. Thus the road achieves a height of 270 m.			pa Hamas po	Officeral Street		
5	(i) Nature of soil				mix of Earth and Boulders, Sol Roack, Hard Rock & Very Hard Rock (ii) None (iii) The Natural Drainage characteristics of the area is good			
-	(ii) Cliffs and gorges.							
	(iii) Drainage characteristics of the area including supceptibility to flooding							
	indicating maximum and minimum				(iv) The elevation at the starting point of the road is 1106 m and the elevation at the end point of the road			
5	(v) Variations extants and types				Nil			
3.8	Climate Condition							
-	(a) Temperature Monthly max. & min. reading.	(a) Temperature Monthly max. & Min reading		(a) Temperature Monthly max. & Min reading.				
0000000	The court of the contract of	Month	Temperal Max	ture (in <sup>0</sup> C)	Month	Temperat Max.	uce (in °C) Min.	
-		January	20	-1	January	20	-1	
5	Frenchisma pointified	February	25	8	February	25	8	
-	Benedimin Parkers	March	28	10	March	28	10	
-	Vi Control of the Con	April	28	15	April	28	15	
9		May	35	20	May	35	20	
		June	36	24	June	36	24	
3		July	32	19	July	32	19	
-		August	30	17	August	28	17	

## Performa for comparison between identified alignments Page 3 of 4

Name of Work :- New Construction of Simli-Sheleshwar Motor Road in Karnprayag Constituency of District Chamoli.

SI.No	Variables	Alignment No-1	Alignment No-2		
5 1	2	3	4		
		(f) The site is exposed to sun throughout the year.	(f) The site is exposed to sun throughout the year. Except 2 to 3 Months.		
	(g) Unusual weather condition like cloud brust etc	(g) There is no record of unsual weather condition like cloud brust in the area where the site is located.	(g) There is no record of unsual weather condition like cloud brust in the area where the site is located.		
9	Facilities resources.	Aserage Rambili	L Average Bornell		
	(a) Landing ground.	(a) None	(a) None		
7	(b) Dropping Zone.	(b) At site	(b)At site		
	(c) Food stuffs.	Ghehun, Aloo, Green Vegetable, Onion etc	, (c) Adrak, Mirch, Lehsoon, Dhan, Ghehun, Aloo, Green Vegetable, Onion etc		
	(d) Labour local availability and need for import.	(d) Local labour is available for costruction work.	(d) Local labour is available for costruction work.		
	(e) Construction material (Timber, Bamboo, Sand, Stone, Shingle etc. extent of their availability and lead involved	work shall be made available locally as it shall be obtained from hill side cutting, However, Sand requried for	work shall be made available locally		
F 10	Value of land, agricultural land, Irrigated land, bult up land, forest land etc,	rest construction of the road in this alignment is as under- As per current Govt. Rate  Value of the land required for the construction of the road in the alignment is as under- As per current Govt. Rate  Value of the land required for the construction of the road in the land required for the land required for the land required for the construction of the land required for the land required fo			
11	Approximate Const. Cost.	Rs 37.80 Lacs	Rs. 40.00 Lacs		
12	Access point indicating possibility of induction of equipment.	Access point available for induction of equipment	f Access point available for induction of equipment		
5 13	Period required for construction.	12 Months	15 Months		
514	Strategic Consideration.	efficient equipment/ Machinery shall	Deployment of skilled manpower an lefficient equipment/ Machinery sha be made for completion of the project		
15	Important villages, towns and markets centers to be connected.		The road shall provide connectivty to village Chatingyala,koti Nauli ,Hinldoli with a population of numbers.		
516	Recreational potential.	Nil	Nil		
17	Economic Factors:		December 200		
5	(a) Population served by the alignment.	(a) 1114	(a) 1114		

## Name of Work :- New Construction of Simli-Sheleshwar Motor Road in Karnprayag Constituency of District Chamoli.

_	Variables	Alignment No-1			Alignment No-2		
	2 (ii) Agricultures and aconomic potential of the area.	3			4		
		September	28	13	September	28	13
		October	18	9	October	18	9
		November	21	5	November	21	5
		December	18	-1	December	18	-1
	(b) Rainfall data average annual peak intensities monthly distribution (to the	(b) Rainfall data average annual peak intensities monthly distribution		(b) Rainfall data average annual per intensities monthly distribution			
	extent available)	Month	Average Rainfall data (in mm)		Month	Average Rainfall data (in-mm)	
	(I) Ming. Such se uproping sites. (ii) Leyrand other problem	January	40		January	40	
		February	33		February	33	
		March	28		March	28	
		April	25		April	25	
		May	2		May	2	
	IEL Payery	June	16		June	16	
	(N) Assisting to contraction for	July	35	William	July	35	124
	collection and carriage of contraction	August	30		August	30	
	Marianal period should for	September	2		September	21	
	construction of work	October	9		October	9	
	Total No. of trees to be removed.	November		7	November	7	
	Avarage Density of lorent cover	December	4		December	4	
	(c) Snowfall data average annual peak intensities monthly distribution (to the extent available)	(c) Snowfall fall data average annual peak intensities monthly distribution			(c) Snowfall fall data average annu peak intensities monthly distribution		
		Month	Average data (i		Month	Average data (ii	
	MEDICAL TO SECURITION OF PROPERTY OF	January	5	0	January	-	
Park I		State of the state			Special State of the second	5	0
The state of the s		February	1	0	February	1	ATTERNATION OF THE PERSON OF T
		February March	1	0	E CLUI AL MINISTER CO.		0
		ALCO PAGE	1	0	February	1	0
		March	1	0	February March	11	0
	The state of the s	March April	-		February March April	11	0
	THE STREET WE	March April May			February March April May June	11	0
	and the separate and	March April May June July		-	February March April May June July	11	0
	tofted softwared the tradition of the tr	March April May June July August			February March April May June July August	-	0
	and the separate and	March April May June July August September			February March April May June July	-	0
	and the separate and	March April May June July August			February March April May June July August September October	-	0
	and the separate and	March April May June July August September Qctober			February March April May June July August September October November	11	0
	and the separate and	March April May June July August September October November	-		February March April May June July August September October		0

Name of Work :- New Construction of Simli-Sheleshwar Motor Road in Karnprayag Constituency of District Chamoli.

SI.No	Variables	Alignment No-1	Alignment No-2		
1	2	3			
	प्रमाणिक विचा	crops by mechanical means (i.e. through road) shall enchance the economical condition of the people residing in this area. Potential of the			
18	other major development projects being taken up electric projects etc.	None			
19	(i) Misc. Such as camping sites	(i) Nil	(i) Nil		
	(ii) Law and other problem	(ii) There is no significant law and (ii) There is no significant law an order problem in the area and the loacl administration takes care of such matters.			
7	(iii) Royalty	(iii) Royalty is paid to the Revenue Department.	(iii) Royalty is paid to the Revenue Department.		
5	(iv) Availability of contractors for collection and carriage of construction material	(iv) Available	(iv) Available		
>	) working period available for (v) 09 Months onstruction of work.		(v) 09 Months		
20	Total No. of trees to be removed .	134 Numbers	Approximately 200 Numbers		
521	Average Density of forest cover .	0.4 (Dense Forest)	0.7 (Dense Forest)		
22	Total No. of Merits				
23	Total No. of Demerits				

RECOMMENDATIONS:

anment no.-1 is recommended for approval being more economical, useful & technically feasible.

कनिष्ठं अभियन्ता प्रान्तीय खण्ड लो**०नि**०िष्ट कर्णप्रयाग सहायक आभयन्त प्रा0ख0लो०नि०वि० कर्णप्रयाग अधिशासी अभ्यन्ता आन्तीय खण्ड लोश नि० वि० कर्णप्रयाग | अमोली ]