


### ABSTRACT OF COST

Name of work:- C/O Link road from Nehra PHC Kainchi to Nagadhar via Growth km 0/000 to 3/146 (SH:- C/O Dumping Places)

Sr. No.	Description	Qty.	Unit	Rate	Amount.
1	Earth work in excavation for structure in all depth as per drawing and technical specification Clause 305-1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable material. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion damage to hill side water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiselling and wedging out of rock( where blasting is prohibited) as directed by the Engineer-in-Charge	78.75	Per Cubic metre	128.15	10092.00
2	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to IS:280 and IS: 4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25Kg each as per drawing and technical specifications Clause 1301 including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	576.00	Per Cubic metre	1458.40	840038.00
				<b>Total:-</b>	<b>850130.00</b>

  
SE


  
Assistant Engineer  
(B&R) Sub Division  
HPPWD Taklech

## ABSTRACT OF COST

Name of work:- C/O Link road from Nehra PHC Kainchi to Nagadhar via Growth km 0/000 to 3/146 (SH:- C/O Dumping Places)

Sr. No.	Description	Qty.	Unit	Rate	Amount.
1	Earth work in excavation for structure in all depth as per drawing and technical specification Clause 305-1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated suitable material. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion damage to hill side water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiselling and wedging out of rock (where blasting is prohibited) as directed by the Engineer-in-Charge	78.75	Per Cubic metre	128.15	10092.00
2	Providing and laying of boulder apron laid in wire crates with 4mm dia G.I. wire conforming to IS:280 and IS: 4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25Kg each as per drawing and technical specifications Clause 1301 including hauling of material in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge.	576.00	Per Cubic metre	1458.40	840038.00
				Total:-	850130.00

  
JTE

  
Assistant Engineer  
(B&R) Sub Division  
HPPWD Takdech

## DETAIL OF MEASUREMENT

Name of Work:- C/O Link road from Nehra PHC Kainchi to Nagadhar via  
Growth km 0/000 to 3/146 (SH:- C/O Dumping places)

Sr. No.	Description of Item	No.	Length	Width	Height /Depth	Quantity
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1					
		1.00	50.00	2.10	0.30	<b>31.5</b>
		1.00	50.00	2.10	0.45	<b>47.25</b>
					<b>Total:-</b>	<b>78.75</b>
2	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I wire 100mm x 100mm					
	Ist Layer	2.00	50.00	2.10	1.20	252.00
	2nd Layer	2.00	50.00	1.50	1.20	180.00
	3rd Layer	2.00	50.00	1.20	1.20	144.00
	<b>Total:-</b>					<b>576.00 Cum</b>

  
K. S. J. E.

## DETAIL OF MEASUREMENT

Name of Work:- C/O Link road from Nehra PHC Kainchi to Nagadhar via  
Growth km 0/000 to 3/146 (SH:- C/O Dumping places)

Sr. No.	Description of Item	No.	Length	Width	Height /Depth	Quantity
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1					
		1.00	50.00	2.10	0.30	31.5
		1.00	50.00	2.10	0.45	47.25
					<b>Total:-</b>	<b>78.75</b>
2	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I wire 100mm x 100mm					
	Ist Layer	2.00	50.00	2.10	1.20	252.00
	2nd Layer	2.00	50.00	1.50	1.20	180.00
	3rd Layer	2.00	50.00	1.20	1.20	144.00
	<b>Total:-</b>					<b>576.00 Cum</b>

  
JE