

TECHNICAL REPORT

Name of Road : NH-8 KM 181 (ANTELA) TO SH-8A (KHACHARIYAWAS-KALYANPURA RENWAL) KM 0/00 TO 13/00

PACKAGE NO. : RJ-16-10-SRF (SH)-2018-19

JOB NO. : 47/5054/SRF/MDR/GEN/2018-19 Rs. = 295.71 Lacs
47/5054/SRF/MDR/SC/2018-19 Rs. = 76.76 Lacs
47/5054/SRF/MDR/ST/2018-19 Rs. = 58.03 Lacs
TOTAL = 430.50 Lacs

Name of Cricle : P.W.D. Rural Circle, Jaipur

Name of Division : P.W.D. Dn Kotputli

Name of Sub Division : P.W.D. Sub Dn Viratnagar-II

A.F. Sanction : F (35) A&F/SRF/Sec.-II/2018-19 D-446 Dated 11-09-2018 Amount (Rs. 430.50 Lacs)

Necessity : This Road is SH-83 which Started From NH-8 Km 181 to end point is on Sikar Distt. Border. Total Length road is 13.00 Km presently this road having 0/00 to 4/600 Km Fully damaged road which is below the Ground Leval at some places so raising is required and Km 11/500 to 13/00 is old PMGSY Road. Km 4/600 to 11/500 is Kutcha Portion. The Rehabilitation of this 6.100 km road is essential balance length be Constructed in Kutcha Portion.


Specification : The following specification has been adopted for this work :
A. Road Work
1 GSB on Berms 150mm thick and 1.00 mtr. width on either side.
2 ~~as per I~~ for Strengthening and for raising 150 mm thick
3 ~~WMM~~ for Strengthening and for raising 250 mm thick
4 20mm PMC with seal coat type B Bitumen (VG-30)
5 Cement concrete M-30 grade, 200 mm thick is taken, as shown in scope of work.
B. Road Furniture taken in estimate as per requirement


Labour : The skilled and unskilled labour is locally available.

B.S.R. : Rates are based on P.W.D. Rural Circle, Jaipur Road BSR effective from March, 2018 with all subsequent Corrigendum

Estimated Cost : Rs. 430.50 Lacs

Agency : This work will be executed by the P.W.D after calling competitive tenders from registered contractors.


Assistant Engineer
P.W.D. Sub Dn Viratnagar-II


Executive Engineer
P.W.D. Dn Kotputli