

Brief Note on the Project of UGSS to Theni-Allinagaram Municipality

Administrative approval is accorded vide GO (D) No. 132 dated 28.02.2011 for Rs.42.09 Crores. The proposal is technically sanctioned on 04.01.2008 for Rs.38.66 Crores. The component of scheme is as detailed below:

- 1) Total length of Collection System (200mm to 600mm) - 56758m
- 2) Total No.of manhole - 2488 Nos.
- 3) Total No.of Lift Manhole - 3 Nos. + 1 (lift station)
- 4) Main pumping station consist of Screen, Grit and Collection well @ back side of Bunglowmedu
- 5) Total length of pumping main (150mm & 600mm) - 3770 m
- 6) Total No.of HSC - 15000 Nos. (90000m)
- 7) Treatment plant Unit with necessary primary- and secondary treatment unit having capacity of 12.05 MLD (intermediate stage) at about 300 m away from the Bund of Mullai Periyar river. 1 No.

Signature :

(Name in Block Letters) :

Designation :

Address (of User agency) :

C.RAJARAM

Municipal Engineer and
Commissioner (i/c)

Theni-Allinagaram Municipality.
Theni.