



सत्यमेव जयते

INDIA NON JUDICIAL

Government of Karnataka

Rs. 4,100


e-Stamp

Certificate No. : IN-KA97003942572857T
 Certificate Issued Date : 06-Apr-2021 05:17 PM
 Account Reference : NONACC (FI)/ kaksfcl08/ HUBLI7/ KA-DW
 Unique Doc. Reference : SUBIN-KAKAKSFCL0865616033573377T
 Purchased by : N I SHETTY PROJECTS PRIVATE LIMITED
 Description of Document : Article 12 Bond
 Description : AGREEMENT
 Consideration Price (Rs.) : 0
 (Zero)
 First Party : N I SHETTY PROJECTS PRIVATE LIMITED
 Second Party : EXECUTIVE ENGINEER PWP AND IWT DIV DHARWAD
 Stamp Duty Paid By : N I SHETTY PROJECTS PRIVATE LIMITED
 Stamp Duty Amount(Rs.) : 4,100
 (Four Thousand One Hundred only)

For MAHANBHARA VIVIDHODDECHA
 SOUHARDA SAHAKARI NIYAMITA, HUBLI

(R)

AUTHORITY SIGNATURE



Please write or type below this line

IP-CE-01/2021-2022/12-04-2021



GOVT. OF KARNATAKA
 (PUBLIC WORKS DEPT DN OFFICE)
AGREEMENT

This agreement, made on the 12 day of April - 2021 between
 Executive Engineer, Public Works Department, Dharwad Division, Dharwad
 Shri. N I SHETTY (N I SHETTY PROJECTS PRIVATE LIMITED) hereinafter called "the
 Contractor") of the other part.

Statutory Alert:

1. The authenticity of this Stamp certificate should be verified at 'www.shcilestamp.com' or using e-Stamp Mobile App of Stock Holding. Any discrepancy in the details on this Certificate and as available on the website / Mobile App renders it invalid.
2. The onus of checking the legitimacy is on the users of the certificate.
3. In case of any discrepancy please inform the Competent Authority.

Item Wise Financial Bid Details

Tender No. : KPWD/2020-21/RD/WORK_INDENT136225

Department : Karnataka Public Works Department

Tender Title : Improvements to Kalakeri To Hunashikumari
Road from Km. 0.00 to 4.10 in Dharwad Taluk
of Dharwad Dist.

Supplier Name : N I SHETTY (NISHETTY PROJECTS PRIVATE LIMITED)

Bid Number : B4295088

Bid Item Details :

Item Code	Item Description	UOM	Quantity	Unit Rate	Amount	Amount In Words
19.2.1	KSRRB 300-1. Earthwork excavation by mechanical means for roads, drains & similar works in all types soils involving an average horizontal through upto 2 mtrs and an average lift upto 1.5 mtr to 2 mtr excavated surface levelled and sides neatly dressed, the dispose earth to be leveled neatly after breaking of clods complete as per specifications.	cum	4182	32.4	135496.8	One Lakh Thirty Five Thousand Four Hundred and Ninety Six (dot) Eight Only.
19.60	KSRRB M300- Construction of Embankment with Material Gravel/ Murrum. KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300- 2 complete as per specifications.(Including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density) MORTH Specification No. 305	cum	3037.5	506.52	1538554.5	Fifteen Lakh Thirty Eight Thousand Five Hundred and Fifty Four (dot) Five Only.
19.61	KSRRB M300-Construction of Embankment with Material deposited from Roadway cutting. KSRRB M300-54. Construction of embankment with approved material deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300-2 complete as per specifications.which includes , watering charges & compaction by vibratory roller) MORTH Specification No. 305	cum	3345.6	102.6	343258.56	Three Lakh Fourty Three Thousand Two Hundred and Fifty Eight (dot) Five Six Only.
19.62	KSRRB M300-Construction of Subgrade and Earthen Shoulders. KSRRB M300-55. Construction of sub-grade and earthen shoulders with approved material Gravel/Murrum with all lifts & leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table No. 300-2 complete as per specifications (including cost of earth, watering charges & compaction by vibratory rollercompaction by vibratory roller to 97% of proctors density) MORTH Specification No. 305	cum	2665	532.44	1418952.6	Fourteen Lakh Eighteen Thousand Nine Hundred and Fifty Two (dot) Six Only.
20.4	Construction of granular sub-base Grading-Vas Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98% proctor density, complete as per specifications. Clause 401 of MORTH V Revision	cum	3280	1881.36	6170860.8	Sixty One Lakh Seventy Thousand Eight Hundred and Sixty (dot) Eight Only.
20.18	KSRRB M400- Wet Mix Macadam KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406	cum	3843.75	2149.2	8260987.5	Eighty Two Lakh Sixty Thousand Nine Hundred and Eighty Seven (dot) Five Only.

Executive Engineer
Public works Department
Dharwad Division, Dharwad

Item
Code

Item Description

UOM Quantity Unit
Rate

21.6 KSRRB M500-6. Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. MORTH Specification No. 502

Sqm 15375 33.13

509375

Friday, 16 April 2021 12:10
APPA B CHOUDANNAVAR - EE
VAD pwn_ee11_dha
Indent Management Ter
Management Reservation

21.2 KSRRB 500-2. Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH specification clause 501

Sqm 4500 5.4

24300

Two
Four
Thousand
Three
Hundred
(dot)
Zero
Only.

21.10 KSRRB M500-10. Providing and applying tack coat using 80/100 grade bitumen(VG10) in boiler fitted with spray set distributor at the rate of 0.20 kg per sqm on the existing prepared bituminous surface cleaned with mchancial broom. complete as per specifications. - using bitumen 80/100 on primed surfaces

Sqm 19875 12.67

251816.25

Two Lakh
Fifty One
Thousand
Eight
Hundred
and
Sixteen
(dot)
Two Five
Only.

21.11.6 KSRRB 500-11. Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixd material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, HOM of machineries complete as per specifications. MORTH /Chapter 5 - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 3.3 % VG-30 Bitumen

cum 993.75 6527.01

6486216.19

Sixty
Four
Lakh
Eighty
Six
Thousand
Two
Hundred
and
Sixteen
(dot) One
Eight
Seven
Five
Only.

21.20.6 KSRRB M500-18. Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 508 complete in all respects complete as per specifications. - using 40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (25 mm to 30 mm) with 5 % VG-30 Bitumen

cum 496.88 8446.83

4197060.89

Fourty
One Lakh
Ninty
Seven
Thousand
and Sixty
(dot)
Eight
Nine Zero
Four
Only.

Back

This site is best viewed in 1024x768 resolution.

Executive Engineer
Public works Department
Dharwad Division, Dharwad

	Item Description	UOM	Quantity	Unit Rate	Amount	Amount In Words
	RB M2500-5.1. Providing and laying Flooring with Rubble stone in em 1:3 over a bed 100mm thick CC bed of 1:2:4 mix proportion including cost of materials, labour, HOM complete as per specifications. MORTH Specification No. 2505	cum	27.42	4999.32	137081.35	One Lakh Thirty Seven Thousand and Eighty One (dot) Three Five Four Four Only.
	KSRRB M2600-3. (ii) Providing & fixing 250 mm wide, 20 mm thick compressible fibre board in expansion joint complete as per drawing & Technical Specification including cost of materials, labour, HOM complete as per specifications. MORTH Specification No. 2605	M	120	128.52	15422.4	Fifteen Thousand Four Hundred and Twenty Two (dot) Four Only.
32.3	KSRRB M2700-3. Construction of RCC railing of M30 Grade in-situ with 20 mm nominal size aggregate, true to line and grade, tolerance of vertical RCC post not to exceed 1 in 500, centre to centre spacing between vertical post not to exceed 2000 mm, leaving adequate space between vertical post for expansion, complete as per approved drawings and technical specifications including cost of materials, labour, HOM complete as per specifications. MORTH Specification No. 2703, 1500, 1600 & 1700	M	43.36	1928.88	83636.24	Eighty Three Thousand Six Hundred and Thirty Six (dot) Two Three Six Eight Only.
32.5	KSRRB M2700-5. Drainage Spouts using 100mm class 'B' GI pipe as per drawing and Technical specification including clamps and nuts etc., including cost of materials, labour, HOM complete as per specifications. MORTH Specification No. 2705	No	4	1747.44	6989.76	Six Thousand Nine Hundred and Eighty Nine (dot) Seven Six Only.
28.10	KSRRB M2200- Providing Weep Holes KSRRB M2200-8. Providing weep holes in Brick masonry I Plain I Reinforced concrete abutment, wing wall I return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing force. Complete as per drawing and Technical Specifications including cost of materials, labour, HOM complete as per specifications. MORTH Specification No.2706 & 2200	Nos/mtr	17.66	169.56	2994.43	Two Thousand Nine Hundred and Ninety Four (dot) Four Two Nine Six Only.
24.52	Providing and fixing RCC precast guard stones of size 0.23mx0.23mx1.5m casted in cc 1:1.5:3 with 20mm down size aggregates using 10mm dia vertical 4TMT steel rods and 8 mm dia stirrups at 20 cm c/c fixed 0.90 m above Ground level using steel moulding, Curing, transportation to work spot including excavation in hard soil fixing in plain cement concrete 1:2:4 using 20mm downsize aggregate including aligning to plumb and line providing enamel painting to exposed faces in alternate black and white strips and painting with reflective paint on top of guard stone with a width of 10 cm including cost of all materials, labour, hire charge of machineries complete. (As per drawing)	Each	120	2751.84	330220.8	Three Lakh Thirty Thousand Two Hundred and Twenty (dot) Eight Only.

Back

This site is best viewed in 1024x768 resolution.

Executive Engineer
Public works Department
Dharwad Division, Dharwad

MAPPA B CHOUDANNAVAR - EE
ARWAD pwn_ee11_dha

Supported Browser Versions are: IE11,
Mozilla Firefox 47,48,49,50 and 51.

Due to Security reasons, use of multi-tab/multi-instance of browser
is disabled in Karnataka Public Procurement Portal.

File Indent Management Tender Management Catalogue Management Payment Contract Management Auction Management
Management Reservation Allocation

Item Wise Financial Bid Details

Department : Karnataka Public Works Department

Tender No. : KPWD/2020-21/RD/WORK_INDENT136225

Tender Title : Improvements to Kalakeri To Hunashikumari
Road from Km. 0.00 to 4.10 in Dharwad Taluk
of Dharwad Dist.

Bid Number : B4295088

Supplier Name : N I SHETTY (NISHETTY PROJECTS PRIVATE LIMITED)

Bid Item Details :

Item Code	Item Description	UOM	Quantity	Unit Rate	Amount	Amount In Words
18.42	KSRRB M200-21.2. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. Removal of all types of Hume pipes and stacking including earthwork and dismantling of masonry works - B. Above 600 mm to 900 mm dia.	M	60	390.96	23457.6	Twenty Three Thousand Four Hundred and Fifty Seven (dot) Six Only.
32.8	KSRRB M2300-16. Providing and laying Cement concrete wearing coat with OPC cement design mix M30 @ 360 kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, and reinforcement at 75 kg/cum with superplasticiser @31ts confirming to IS9103-1999 Reaffirmed-2008 including cost of reinforcement complete as per drawing and Technical Specifications including cost of materials, labour, HOM complete as per specifications. MORTH Specification No. 2702	Cum	16.26	11822.98	192241.65	One Lakh Ninety Two Thousand Two Hundred and Forty One (dot) Six Five Four Eight Only.
18.27	KSRRB M200-15.2. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. iii) Dismantling Stone Masonry.B. Rubble stone masonry in cement mortar. MORTH Specification No. 202	cum	43.48	379.08	16482.4	Sixteen Thousand Four Hundred and Eighty Two (dot) Three Nine Eight Four Only.
27.4	"KSRRB M2100-2.1. Earth work in excavation for foundation of structures as per drawing and technical specifications, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material complete as per specifications. B. Mechanical Means (i) Depth upto 3 m" MORTH Specification No. 304	cum	1191.82	54.0	64358.28	Sixty Four Thousand Three Hundred and Fifty Eight (dot) Two Eight Only.
27.5	"KSRRB M2100-2.2. Earth work in excavation for foundation of structures as per drawing and technical specifications, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material complete as per specifications. B. Mechanical Means (ii) Depth 3 m to 6 m" MORTH Specification No. 304	cum	6.44	61.56	396.45	Three Hundred and Ninety Six (dot) Four Four Six Only.
2.15	KSRRB 2.8 : Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications. specification. No. KBS	cum	210.7	2314.44	487652.51	Four Lakh Eighty Seven Thousand Six Hundred and Fifty Two (dot) Five Zero Eight Only.
27.18	KSRRB M2100 PCC 1 KSRRB M2100-10. Plain cement concrete M10 with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @ 0.56cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days complete as per specifications MORTH Specification No. 2100	cum	74.56	5943.67	443160.04	Four Lakh Forty Three Thousand One Hundred and Sixty (dot) Zero Three Five Two Only.

Executive Engineer
Public works Department
Dharwad Division, Dharwad