

Office of Empanelled Geologist

पत्रांक 622 / 148व्यक-सा0 / 13 दिनांक 15 / 05 / 2013

P.W.D. Uttarakhand

Geological Investigation Report

E.G. – Road / Bridge / Alignment

I.D, PMGSY, Purola – 03 / 2016

**Geological Assessment of the Alignment Corridor Proposed For Gundiya
Gaon to Syaluka Motor Road in Distt. Uttarkashi**

15 Jan. 2016

**J.P. Madhwal
Empanelled Geologist
Shantikunj, Lane-1,
Nehrugram Road,
Nathanpur, Dehradun
Phone – 0135 – 6448774
Mob – 9412965965
Email – jpmadhwal@gmail.com**


**Geological Assessment of the Alignment Corridor Proposed For Gundiya
Gaon to Syaluka Motor Road in Distt. Uttarkashi**

J.P. Madhwal
15/01/2016

Introduction :- The I.D, PMGSY, Purola, has proposed the construction of 7.750 Km. long motor road named Gundiya Gaon to Syaluka motor road under PMGSY Project on the request of the Executive Engineer, I.D, PMGSY, Purola. I carried out the geological assessment of the proposed alignment of the road in presence of the person of Praveen Rawat Engineering Consultant, D.Dun on Dated 08/01/2016.

- 1. Location:-** The proposed alignment originates from the Km. 01 of Gundiya Gaon Rama Motor Road as a Branch Road. Four H.P. Bends has been proposed for the said road.
- 2. Geological Assessment:-** Geologically the area of the proposed road is located in the inner lands of Lesser Himalaya Belt which is mostly occupied by the rocks of Jaunsar Group. The Quartzite with Augen Gneiss are exposed along the alignment. These rocks are massive to thinly bedded, soft to very hard, compact and partially weathered in nature.

Four prominent and one random joints set in addition to minor shear zone traverse these rocks and control the stability of the various slope facets of the alignment passes are inclined at moderate to steep angle and these are partially covered with the overburden material of varying thickness ranging from 0.5 m to 1.5 m thick. The rock mass exposed along the alignment corridor is mostly hard and its "Uniaxial Compressive Strength" has been estimated ranging between 50 M Pa to 100 M Pa (ISRM Manual Index). By and large the joints traversing the rock masses are widely spaced through except at places where the rocks is sheared and shattered. The values of the Rock Quality Designation (RQD) calculated at the site ranging between 71 percent to 90 percent suggests that the slope forming rock masses are less distressed in nature and decrease the risks of instability. All the joints planes of the rocks are rough to moderately smooth, tight and sometimes sealed with the secondary inclusion.


J. P. MADHWAL
M.Sc. GEOLOGY
EMPANELLED GEOLOGIST
P.W.D. UTTARAKHAND

The details of the joints recorded at the site are given in the following table:-

Table

S. No.	Feature	Dip angle	Azimuth
1	2	3	4
J ₁	(S ₀ Bedding Joint)	35 ⁰	N185
J ₂	(S ₁ Foliation Joint)	20 ⁰	N175
J ₃	(Random Joint Set)	30 ⁰	N240
J ₄	(Sealed with Quartzite's)	55 ⁰	N265
J ₅	Joint	45 ⁰	N300

The overburden material exposed along the alignment corridor is comprised of the scanty rock fragments of various shapes and sizes embedded in the clay- silt matrix. This overburden material is naturally well compacted and dense in nature.

The slope forming overburden materials do not contain any soft/dispersive soils.

By and large the alignment slopes are stable and do not bear any signature of mass wasting/land sliding.

On the basis of the geological / geotechnical studies carried at the site and the facts mentioned above the following recommendations are being made for the construction of the proposed road.


3. Recommendation:-

- (i) The alignment some time traverses along/across minor fault zone which is geologically fragile and special attention needs to be given for stability of road where alignment crossing the Nalas or Gads or Local streams.
- (ii) The hill slope is another factor responsible for geological hazards; the road basically traverses the slope class 34⁰ to 55⁰ special attention needs to be given for stability where it is 48⁰ to 60⁰ in some parts.
- (iii) Special attention must be give at the point of H.P. Bend at the time of construction of road.
- (iv) Do not dispose the debris in hill side, dispose it in a safe zone.


J. P. MADHWAL

- (v) Do not blast heavily on the rocks and blasting is restricted near the human settlement / public property.
- (vi) The road must have extra wide lined long drain with adequate cross drainage arrangement.
- (vii) The road must be formed shoulder to shoulder paved, this is so to check the water ingress into the sub surface material.
- (viii) Construct suitably designed retaining walls / Brest wall all along the road, it is essential for the overall stability of the hill slope.
- (ix) All the construction activity must be carried out as per the standards and norms following the IS codes prescribed for the similar civil construction in Himalayan Zone.
- (x) This report is prefeasibility report. At the time of construction it need separate geological concern.

4. Conclusion:- On the basis of the geological / geotechnical studies carried at the site and with the above recommendations, the site was found geologically suitable for the construction of 7.750 Km. long motor road named Gundiya Gaon to Syaluka motor road, Distt. Uttarkashi, Uttarakhand.


(J.P. Madhwal)
J. P. MADHWAL
M.Sc. GEOLOGY
EMPANELLED GEOLOGIST
P.W.D. UTTARAKH