

**XEN, UP JAL NIGAM
JHANSI**

Sub : Permission for laying of U/G Water pipe (400 mm dia casing with 200 mm carrier dia) crossing at Km 1163/13-15 between CGN-NDK stations on JHS-CNB section, through trenchless pipe pushing method by M/s XEN, UP JAL NIGAM JHANSI

Ref : Your Application ID no. NCR/JHS/2021-WL-59

Permission for laying of U/G Water Pipe xing (400 mm dia casing with 200 mm carrier dia) crossing at Km 1163/13-15 between CGN-NDK stations on JHS-CNB section is hereby provisionally granted, subject to the confirmation/clearance of authenticity of BG submitted by you.

Following precautions to be taken while laying Water pipe crossing on Railway land:-

1. The work shall be completed within five days after starting the work, else extra amount will be charged as detention charges as per report of Railway Engineers at site.
2. Before starting the work on railway land ADEN/HQ-I is to be contacted and the work should be carried out under the supervision of SSE/PW & S&T and Electrical staff concerned.
3. Water pipe crossing casing shall be laid up to railway boundary on either side of the railway track.

4- Water pipe crossing should be laid through Trenchless pipe pushing method only, the casing pipe will be inserted simultaneously with boring to keep formation supported all the time to prevent any settlement of track, as per attached approved drawing (DRM/W/JHS/SK/2021-WL-59). Work should completed in all respect within six months.

All other formalities shall be ensured as per direction of railway Engineer Incharge subject to Railway rules terms and condition etc., amended time to time & mentioned in Drg. & RDSO guide lines.

DA- Copy of approved Drg. Agreements & RDSO guide lines (Report No. BS-105).

Kapil Singh
Sr. DEN/C/JHS

C/- Sr.DFM/JHS – For information please, with copy & Agreement.

C/- ADEN/HQ-I - For information and necessary action & advise the date of start and completion of Work.

No. JHS/W/Land/NOC/C/Water pipe xing/2021-WL-60

Date 05.07.2022

**XEN, UP JAL NIGAM
JHANSI**

Sub : Permission for laying of U/G Water pipe (400 mm dia casing with 200 mm carrier dia) crossing at Km 1170/25-27 between CGN-NDK stations on JHS-CNB section, through trenchless pipe pushing method by M/s XEN, UP JAL NIGAM JHANSI

Ref : Your Application ID no. NCR/JHS/2021-WL-60

Permission for laying of U/G Water Pipe xing (400 mm dia casing with 200 mm carrier dia) crossing at Km 1170/25-27 between CGN-NDK stations on JHS-CNB section is hereby provisionally granted, subject to the confirmation/clearance of authenticity of BG submitted by you.

Following precautions to be taken while laying Water pipe crossing on Railway land:-

1-The work shall be completed within five days after starting the work, else extra amount will be charged as detention charges as per report of Railway Engineers at site.

2-Before starting the work on railway land ADEN/HQ-I is to be contacted and the work should be carried out under the supervision of SSE/PW & S&T and Electrical staff concerned.

3-Water pipe crossing casing shall be laid up to railway boundary on either side of the railway track.

4- Water pipe crossing should be laid through Trenchless pipe pushing method only, the casing pipe will be inserted simultaneously with boring to keep formation supported all the time to prevent any settlement of track, as per attached approved drawing (DRM/W/JHS/SK/2021-WL-60). Work should completed in all respect within six months.

All other formalities shall be ensured as per direction of railway Engineer Incharge subject to Railway rules terms and condition etc., amended time to time & mentioned in Drg. & RDSO guide lines.

DA- Copy of approved Drg. Agreements & RDSO guide lines (Report No. BS-105).


Sr. DEN/C/JHS

C/- Sr.DFM/JHS – For information please, with copy & Agreement.

C/- ADEN/HQ-I - For information and necessary action & advise the date of start and completion of Work.



No. JHS/W/Land/NOC/C/Water pipe xing/2021-26

XEN, UP JAL NIGAM
JHANSI

Sub : Permission for laying of U/G Water pipe (500 mm dia casing with 150 mm carrier dia) crossing at Km 1159/31-33 between CGN-NDK stations on JHS-CNB section, through trenchless pipe pushing method by M/s XEN, UP JAL NIGAM JHANSI-284001 (UP).

Ref : Your Application ID no. NCR/JHS/2021-26

Permission for laying of U/G Water Pipe xing (500 mm dia casing with 150 mm carrier dia) crossing at Km 1159/31-33 between CGN-NDK stations on JHS-CNB section is hereby provisionally granted, subject to the confirmation/clearance of authenticity of BG submitted by you.

Following precautions to be taken while laying Water pipe crossing on Railway land:-

- 1-The work shall be completed within five days after starting the work, else extra amount will be charged as detention charges as per report of Railway Engineers at site.
- 2-Before starting the work on railway land ADEN/HQ-I/JHS is to be contacted and the work should be carried out under the supervision of SSE/PW & S&T and Electrical staff concerned.
- 3-Water pipe crossing casing shall be laid up to railway boundary on either side of the railway track.
- 4- Water pipe crossing should be laid through Trenchless pipe pushing method only, the casing pipe will be inserted simultaneously with boring to keep formation supported all the time to prevent any settlement of track, as per attached approved drawing (DRM/W/JHS/SK/2021-26). Work should be completed in all respect within six months.

All other formalities shall be ensured as per direction of railway Engineer Incharge subject to Railway rules terms and condition etc., amended time to time & mentioned in Drg. & RDSO guide lines.

DA- Copy of approved Drg. Agreements &
RDSO guide lines (Report No. BS-105).


Sr. DEN/C/JHS

C/- Sr.DFM/JHS – For information please, with copy & Agreement.

C/- ADEN/HQ-I/JHS - For information and necessary action & advise the date of start and completion of Work.


(रणविजय सिंह)
अधिशासी अभियन्ता
निर्माण खण्ड
उ०प्र० जल निगम, झाँसी।



मंडल रेल प्रबंधक कार्यालय
इंजीनियरिंग शाखा, झाँसी
DRM Office
Engineering Branch, Jhansi

No. JHS/W/Land/NOC/C/Water pipe xing/2021-28

Date-29.06.2022

XEN, Minor irrigation
UPJN Rular Jhansi (U.P.)

Murda wadi to Bajhera cross
Bajhera cross to Mulana village.

Sub : Permission for laying of U/G Water pipe (700 mm dia casing with 200 mm carrier dia) crossing at Km 1156/26-28 between PIC-CGN stations on JHS-CNB section, through trenchless pipe pushing method by M/s XEN, Minor irrigation UPJN Rular Jhansi (U.P.).

Ref : Your Application ID no. NCR/JHS/2021-28 dated 20.02.2021

Permission for laying of U/G Water Pipe xing (700 mm dia casing with 200 mm carrier dia) crossing at Km 1156/26-28 between PIC-CGN stations on JHS-CNB section is hereby provisionally granted, subject to the confirmation/clearance of authenticity of BG submitted by you.

Following precautions to be taken while laying Water pipe crossing on Railway land:-

- 1-The work shall be completed within five days after starting the work, else extra amount will be charged as detention charges as per report of Railway Engineers at site.
- 2-Before starting the work on railway land ADEN/ HQ-I is to be contacted and the work should be carried out under the supervision of SSE/PW & S&T and Electrical staff concerned.
- 3-Water pipe crossing casing shall be laid up to railway boundary on either side of the railway track.
- 4-Water pipe crossing should be laid through Trenchless pipe pushing method only, the casing pipe will be inserted simultaneously with boring to keep formation supported all the time to prevent any settlement of track, as per attached approved drawing. Work should be completed in all respect within six months.

All other formalities shall be ensured as per direction of railway Engineer Incharge subject to Railway rules terms and condition etc., amended up to date & mentioned in Drg. & RDSO guide lines.

DA- Copy of approved Drg. Agreements & RDSO guide lines (Report No. BS-105).

Katil Singh
29/6/22
Sr. DEN/CJHS

C/- Sr.DFM/JHS – For information please, with copy & Agreement.

C/- ADEN/HQ-I - For information and necessary action & advise the date of start and completion of Work.



मंडल रेल प्रबंधक कार्यालय
इंजीनियरिंग शाखा, झांसी
DRM Office
Engineering Branch, Jhansi

No. JHS/W/Land/NOC/C/Water pipe xing/2021-29

Date-29.06.2022

XEN Minor irrigation
UPJN Rular Jhansi (U.P.)

Scmri csp to parghane est
parghane csp to parghane village

Sub : Permission for laying of U/G Water pipe (500 mm dia casing with 200 mm carrier dia) crossing at Km 1173/1-3 between NDK-MOTH stations on JHS-CNB section, through trenchless pipe pushing method by M/s XEN, Minor irrigation UPJN Rular Jhansi (U.P.).

Ref : Your Application ID no. NCR/JHS/2021-29 dated 20.02.2021

Permission for laying of U/G Water Pipe xing (500 mm dia casing with 200 mm carrier dia) crossing at Km 1173/1-3 between NDK-MOTH stations on JHS-CNB section is hereby provisionally granted, subject to the confirmation/clearance of authenticity of BG submitted by you.

Following precautions to be taken while laying Water pipe crossing on Railway land:-

- 1-The work shall be completed within five days after starting the work, else extra amount will be charged as detention charges as per report of Railway Engineers at site.
- 2-Before starting the work on railway land ADEN/ HQ-I is to be contacted and the work should be carried out under the supervision of SSE/PW & S&T and Electrical staff concerned.
- 3-Water pipe crossing casing shall be laid up to railway boundary on either side of the railway track.
- 4-Water pipe crossing should be laid through Trenchless pipe pushing method only, the casing pipe will be inserted simultaneously with boring to keep formation supported all the time to prevent any settlement of track, as per attached approved drawing. Work should be completed in all respect within six months.

All other formalities shall be ensured as per direction of railway Engineer Incharge subject to Railway rules terms and condition etc.. amended up to date & mentioned in Drg. & RDSO guide lines.

DA- Copy of approved Drg. Agreements & RDSO guide lines (Report No. BS-105).

Kapil Singh
29/6/22
Sr. DEN/C/JHS

C/- Sr.DFM/JHS – For information please, with copy & Agreement.

C/- ADEN/HQ-I - For information and necessary action & advise the date of start and completion of Work.