| 240400.13 | | | Grand Total of reclamation required to be deposited (18+19+20): | 21 |
|-----------------------------------|---------------------------------|---|---|---------|
| 34342.88 | | | Departmental Charges @17.50% | 20 |
| 9812.25 | | | Contigency @ 5% | 19 |
| 196245.00 | | | Total reclamation cost (16+17) | 18 |
| .00 | | | Cost of reclamation for site 2. | 17 |
| 196245.00 | | | Cost of reclamation for site 1. | 16 |
| 400500.00 | | | or Say | 15 |
| 400439.17 | | | Total cost of 1 Hact reclamation of dumping site (4+9+13) | 14 |
| 45000.00 | | | Total (10+11+12) | 13 |
| 25000.00 | | | 3rd to 7th Year Maintenance | 12 |
| 10000.00 | | | 2nd Year Maintenance | 11 |
| 10000.00 | | | 1st Year Maintenance | 10 |
| 285000.00 | | | Total(5+6+7+8) | 9 |
| 25000.00 | | | Sowing of grass and bio engineering species . | 8 |
| 100000.00 | | | Misc. Soil Conservation Works | 7 |
| 110000.00 | 100 | 1100 | Cost of Plant (Tall Plant+carriage of tall plant) | 6 |
| 50000.00 | | | Planting Cost (Including carriage of soil and manure) | 5 |
| 70439.17 | | | Total (1+2+3) | 4 |
| 21000.00 | 7000.00 | 3 | Cost of Barbed Wire (7 stand) | ω |
| 40000.00 | 500 | 80 | Cost of RCC Fence Posts | 2 |
| 9439.17 | | | Survey, Demarcation & Fencing Cost | 1 |
| Cost | Unit | Area/ Quantity | Name of component | Sr. |
| | | | Cost for reclamation of 1 Hact of dumping site | Cost fo |
| | 0 | 0.49 | Area of dumping site (in Hact) | |
| | 0 | Solag Rorri | Name of dumping site | |
| n Solag Rorri, 120 in District | Link road from ad Km 0/0 to 5/: | Construction of Link road from Solag Rorri, Kohal to Jurasi road Km 0/0 to 5/120 in District Bilaspur, Himachal Pradesh | Name of Proposal | |
| aspur | HPPWD, Division-II Bilaspur | HPPWD, | Name of User Agency | |
| | | te | Reclamation of muck dumping site | |
| | | | | |

