

TECHNICAL REPORT

Name of Work	: CONSTRUCTION OF CC ROAD FROM TRIVENI ROAD TO BRAHMANI MATA TEMPLE KM. 0/00 TO 0/600
JOB NO.	: 752/5054/New Road/Plan/GN/2018-19 Rs. 24.73 752/5054/New Road/Plan/SC/2018-19 Rs. 6.42 752/5054/New Road/Plan/ST/2018-19 Rs. 4.85
PACKAGE NO.	: RJ-16-15/NEW ROAD/PLAN/2018-19
Scope of work	: BT - 0.145, Interlocking Tile - 0.30 Total : 0.445 and Protection work
Name of Division	: P.W.D. Distt. Dn. Shahpura, Jaipur
Name of Sub Division	: P.W.D. Sub. Dn. Shahpura
A.F. Sanction	: एफ.7(69)/अनु.-2/2018-19 डी-10 दिनांक 11.04.2018 RS : 36.00 Lacs
Necessity	: Brahmani Mata Temple is old Temple and Religious place hence it is necessary to provide approach road upto temple.
Specification For BT Road	: The following specification has been adopted for this work : 1 Sub base - GSB 10 Cm 2 Base Course Gr.1 75mm thick 3 Base Course Gr.2 75mm thick 4 20mm PMC with Seal Coat type B (VG-30) over Primer and tack Coat
CC Road	: 5 PCC 1:3:6 (75mm thick) 6 Interlocking tile M-30 100 Thick 7 Road Furniture taken in estimate as per requirement 8 Compensation Provision for Forest lane Ch. 0/028 to 0/445 (0.562 Hect.) taken LS Rs 5.00 Lacs in Estimate.
Labour	: The skilled and unskilled labour is locally available.
B.S.R.	: Rates are based on P.W.D. Rural Circle, Jaipur BSR effective from March, 2018 with all subsequent Corrigendum
Estimated Cost	: Rs. 36.00 Lacs
Agency	: This work will be executed by the P.W.D after calling competitive tenders from registered contractors.


ASSISTANT ENGINEER
P.W.D. SUB. DN. SHAHPURA

