



To,  
M/s Bihar Engineers and Supplies,  
Saguna more Danapur Cant,Patna  
No. DET-Nal/OFC – Const/WO/2021-2022/04

Date : 25/04/2021

Sb:- Work Order for OFC Laying and associated work by combined Method (HDD, Open Trenching & Splicing) in the OFC Rote from from AsthawaTE to Bihar Sharif TE OFC Route

As per AGREEMENT NO. ENG-N-148/OFC /CONSTRUCTION/2018-19/36 dated 27.04.2019 you are hereby advised to carry out OFC Laying work in OFC route from AsthawaTE to Bihar Sharif TE OFC Route as per detail given below

Sl.No.	PARTICLARS	Qty ( Approx)
01	PLB PIPE LAING BY.Horizontal Boring (HDD)	6500 M
02	Excavating trenches up to a depth of 1.65 m and back filling the excavated trenches after laying the HDPE/PLB pipe with of without protection as per tender specification.	6000 M
03	Laying of PLB/ HDPE Pipes Coils, Coupled with coupler & drawing of PP Nylon Rope through it	12500 M
04	<b>Cable laying by Pulling/blowing</b>	13000M
05	<b>Splicing termination of OF Cable</b>	10 nos.
06	Digging of Pits for jointing chamber, supply and fixing of Pre Cast RCC chambers ,clean sand filling, supply & placing of pre cast RCC slab and back filling of jointing Pit ( Joint Chamber is of 100 cm X 110 cm X 50 cm ) ( Inner Dia x outer Dia x height )	10 nos.
07	Digging of Pits 1 meter toward jungle site on each manhole/joint chamber for fixing of route/joint indicator, fixing and concreting of routes/joint indicator, painting & sign writing of route/joint indicator (indicator)	70 nos

Period :90 days

Site Incharge :- Sh. UMESH KUMAR JTO TX (Bihar Sharif )

Estimate No. : Under Process

Copy to :-

1. THE PGM PTD
2. THE DGM BRF/TX/PLG PTD
3. THE AGM PLG PTD
4. JTO TX BIHAR SHARIF
5. SDE STORES GARDANIBAGH PTD PATNA
6. OFFICE COPY

DET Nalanda, BIHARSARIF

D. B. T. Nalanda  
D.S.N.L. Bihar Svc.

DET Nalanda, BIHARSARIF

D.S.N.L. Bihar Svc.

Registered & Corporate Office

Bharat Sanchar Bhavan, Harish Chandra Mathur Lane Janpath, New Delhi-110 001 (CIN) :U74899DL2000GOI107739





To,  
M/s Bihar Engineers and Supplies,  
Saguna more Danapur Cant, Patna  
No. DET-Nal/OFC – Const/WO/2021-2022/03

Date : 25/04/2021

Sb:- Work Order for OFC Laying and associated work by combined Method (HDD, Open Trenching & Splicing) in the OFC Rote from from AsthawaTE to Benar TE OFC Route

As per AGREEMENT NO. ENG-N-148/OFC /CONSTRUCTION/2018-19/36 dated 27.04.2019 you are hereby advised to carry out OFC Laying work in OFC route from AsthawaTE to Benar TE OFC Route as per detail given below

Sl.No.	PARTICULARS	Qty ( Approx)
01	PLB PIPE LAINING BY Horizontal Boring (HDD)	1970 M
02	Excavating trenches up to a depth of 1.65 m and back filling the excavated trenches after laying the HDPE/PLB pipe with or without protection as per tender specification.	4000 M
03	Laying of PLB/ HDPE Pipes Coils, Coupled with coupler & drawing of PP Nylon Rope through it	5970 M
04	<b>Cable laying by Pulling/blowing</b>	6500M
05	<b>Splicing termination of OF Cable</b>	7 nos.
06	Digging of Pits for jointing chamber, supply and fixing of Pre Cast RCC chambers, clean sand filling, supply & placing of pre cast RCC slab and back filling of jointing Pit ( Joint Chamber is of 100 cm X 110 cm X 50 cm ) ( Inner Dia x outer Dia x height )	7 nos.
07	Digging of Pits 1 meter toward jungle site on each manhole/joint chamber for fixing of route/joint indicator, fixing and concreting of routes/joint indicator, painting & sign writing of route/joint indicator (indicator)	35 nos


Period : 90 days


Site Incharge :- Sh. UMESH KUMAR JTO TX (Bihar Sharif )

Estimate No. FA/20/003734.04

Copy to :-

1. THE PGM PTD
2. THE DGM BRF/TX/PLG PTD
3. THE AGM PLG PTD
4. JTO TX BIHAR SHARIF
5. SDE STORES GARDANIBAGH PTD PATNA
6. OFFICE COPY

  
25/4/2021  
DET Nalanda, BIHARSARIF  
D. B. T. Nalanda  
S.S.N.L. Bihar Sharif

  
25/4/2021  
DET Nalanda, BIHARSARIF  
D. B. T. Nalanda  
S.S.N.L. Bihar Sharif





To,  
M/s Bihar Engineers and Supplies,  
Saguna more Danapur Cant, Patna  
No. DET-Nal/OFC – ConstWO/2021-2022/07

Date : 25/04/2021

Sb:- Work Order for OFC Laying and associated work by combined Method (HDD, Open Trenching & Splicing) in the OFC Rote from Benar TE to Sarmera TE OFC Route

As per AGREEMENT NO. ENG-N-148/OFC /CONSTRUCTION/2018-19/36 dated 27.04.2019 you are hereby advised to carry out OFC Laying work in OFC route from Benar TE to Sarmera TE OFC Route as per detail given below

Sl.No.	PARTICULARS	Qty ( Approx)
01	PLB PIPE LAINING BY Horizontal Boring (HDD)	5000 M
02	Excavating trenches up to a depth of 1.65 m and back filling the excavated trenches after laying the HDPE/PLB pipe with or without protection as per tender specification.	14000 M
03	Laying of PLB/ HDPE Pipes Coils, Coupled with coupler & drawing of PP Nylon Rope through it	14000 M
04	<b>Cable laying by Pulling/blowing</b>	19590M
05	<b>Splicing termination of OF Cable</b>	17 nos.
06	Digging of Pits for jointing chamber, supply and fixing of Pre Cast RCC chambers, clean sand filling, supply & placing of pre cast RCC slab and back filling of jointing Pit ( Joint Chamber is of 100 cm X 110 cm X 50 cm ) ( Inner Dia x outer Dia x height )	15 nos.
07	Digging of Pits 1 meter toward jungle site on each manhole/joint chamber for fixing of route/joint indicator, fixing and concreting of routes/joint indicator, painting & sign writing of route/joint indicator (indicator)	100 nos

Period : 120 days

Site Incharge :- Sh. UMESH KUMAR JTO TX (Bihar Sharif)

Estimate No. FA/21/000841.05

DET Nalanda, BIHARSARIF

D. B. T. Nalanda

B.S.N.L. Bihar sup.

Copy to :-

1. THE PGM PTD
2. THE DGM BRF/TX/PLG PTD
3. THE AGM PLG PTD
4. JTO TX BIHAR SHARIF
5. SDE STORES GARDANIBAGH PTD PATNA
6. OFFICE COPY

DET Nalanda, BIHARSARIF

D. B. T. Nalanda

B.S.N.L. Bihar sup.

Registered & Corporate Office

Bharat Sanchar Bhavan, Harish Chandra Mathur Lane Janpath, New Delhi-110 001 (CIN) U74899DL2000GOI107739

a. B1