

BHARAT SANCHAR NIGAM LIMITED
(A Govt. of India Enterprise)
Off DIVISIONAL ENGINEER (TELECOM)
BIHARSHARIF, NALANDA,
Bihar-803101
Telephone No. 06112-231555
Email-detnalananda.bsnt@gmail.com



भारत संचार निगम लिमिटेड
(भारत सरकार का उपक्रम)
BHARAT SANCHAR NIGAM LIMITED
(A Govt. of India Enterprise)

To
M/S YUVA INFRA TECH PVT. LTD.
IAS COLONY, KIDWAIPURI, PATNA
No. DET-Nal/OFC - Const/WO/2021-2022/02

Date: 23/04/2021

Sb:- Work Order for OFC Laying and associated work by combined Method (HDD, Open Trenching & Splicing) in the OFC Route from Bihar Sarif BSNL TE to Nalanda TE.

As per AGREEMENT NO. ENG-N-148/OFC /CONSTRUCTION/2018-19/37 dated 27/04/2019 you are hereby advised to carry out OFC Laying work in OFC route from Bihar Sarif TE to Nalanda TE as per detail given below

Sl.No.	PARTICULARS	Qty. (Approx)
01	PLB PIPE LAINING BY Horizontal Boring (HDD)	4.0 KM
02	Excavating trenches up to a depth of 1.65 m and back filling the excavated trenches after laying the HDPE/PLB pipe with or without protection as per tender specification	10.0 KM
03	Laying of PLB/HDPE Pipes Coils, Coupled with coupler & drawing of PP Nylon Rope through it	10.0 KM
04	Cable laying by Pulling/blowing	15.0 KM
05	Splicing termination of OF Cable	12 nos.
06	Digging of Pits for jointing chamber, supply and fixing of Pre Cast RCC chambers, clean sand filling, supply & placing of pre cast RCC slab and back filling of jointing Pit (Joint Chamber is of 100 cm X 110 cm X 50 cm) (Inner Dia x outer Dia x height)	10 nos.
07	Digging of Pits 1 meter toward jungle site on each manhole/joint chamber for fixing of route/joint indicator, fixing and concreting of routes/joint indicator, painting & sign writing of route/joint indicator (indicator)	80 nos.

Period : 60 days

Site Incharge - Sh. VEDPRAKASH JTO TX (Rajgir)

Estimate No. FA/18/010017/03

Copy to :-

1. THE PGM PTD
2. THE DGM BRF/TX/PLG PTD
3. THE AGM PLG PTD
4. JTO TX RAJGIR
5. SDE STORES GARDANIBAGH PTD PATNA
6. OFFICE COPY

DET Nalanda, BIHARSARIF

DET, NALANDA
BSNL BIHAR SHARIF

DET Nalanda, BIHARSARIF

Registered & Corporate Office

Bharat Sanchar Bhavan, Harish Chandra Mathur Lane Janpath, New Delhi-110 001 (CIN): U74899DL2000GOI107730

S.S.N.L. Bihar Div

BHARAT SANCHAR NIGAM LIMITED
(A Govt. of India Enterprise)
O&S DIVISIONAL ENGINEER (TELECOM)
BIHARSHARIF, NALANDA,
Bihar-803101
Telephone No. 06112-231535
Email: detnalanda,bsnl@gmail.com



भारत संचार निगम लिमिटेड
(भारत सरकार का उद्यम)
BHARAT SANCHAR NIGAM LIMITED
(A Govt. of India Enterprise)

To
M/S YUVA INFRA TECH PVT. LTD.
IAS COLONY, KIDWAIPURI PATNA
No. DET-Nal/OFC - Const/WO/2021-2022/03

Date: 23/04/2021

Sb.- Work Order for OFC Laying and associated work by combined Method (HDD, Open Trenching & Splicing) in the OFC Route from Bihar Sarif BSNL TE to Nalanda TE.

As per AGREEMENT NO. ENG-N-148/OFC /CONSTRUCTION/2018-19/37 dated 27.04.2019 you are hereby advised to carry out OFC Laying work in OFC route from Nalanda TE TO SILAO as per detail given below

Sl.No.	PARTICULARS	Qty (Approx)
01	PLB PIPE LAYING BY Horizontal Boring (HDD)	2.0 KM
02	Excavating trenches up to a depth of 1.65 m and back filling the excavated trenches after laying the HDPE/PLB pipe with or without protection as per tender specification.	3.8.0KM
03	Laying of PLB/ HDPE Pipes Coils, Coupled with coupler & drawing of PP Nylon Rope through it	3.8.0KM
04	Cable laying by Pulling/blowing	7.0KM
05	Splicing termination of OF Cable	05 nos.
06	Digging of Pits for jointing chamber, supply and fixing of Pre Cast RCC chambers, clean sand filling, supply & placing of pre cast RCC slab and back filling of jointing Pit (Joint Chamber is of 100 cm X 110 cm X 50 cm) (Inner Dia x outer Dia x height)	05 nos.
07	Digging of Pits 1 meter toward jungle site on each manhole/joint chamber for fixing of route/joint indicator, fixing and concreting of routes/joint indicator, painting & sign writing of route/joint indicator (indicator)	32 nos

Period : 50 days

Site Incharge :- Sh. VEDPRAKASH JTO TX (Rajgir)

Estimate No. FA/18/010017/02

Copy to :-

1. THE PGM PTD
2. THE DGM BRF/TX/PLG PTD
3. THE AGM PLG PTD
4. JTO TX RAJGIR
5. SDE STORES GARDANIBAGH PTD PATNA
6. OFFICE COPY

DET Nalanda, BIHARSARIF
DET, NALANDA
BSNL BIHAR SHARIF

DET Nalanda, BIHARSARIF

Registered & Corporate Office

Bharat Sanchar Bhavan, Hansi Chandra Mathur Lane Janpath, New Delhi-110 501 (GIN):U74699DL2000GC110749

O. E. I. Nalanda
S.S.M.L. Bihar Sharif

BHARAT SANCHAR NIGAM LIMITED
(A Govt. of India Enterprise)
O/o DIVISIONAL ENGINEER (TELECOM)
BIHARSARIF, NALANDA,
Bihar-803101
Telephone No. 06112-231555
Email: detnalanda.bsnl@gmail.com



भारत संचार निगम लिमिटेड
(भारत सरकार का उपक्रम)
BHARAT SANCHAR NIGAM LIMITED
(A Govt. of India Enterprise)

To
M/S YUVA INFRA TECH PVT. LTD.
IAS COLONY, KIDWAIPURI, PATNA
No. DET-Nal/OFC - Const/WO/2021-2022/04

Date: 23/04/2021

Sb:- Work Order for OFC Laying and associated work by combined Method (HDD, Open Trenching & Splicing) in the OFC Route from Bihar Sarif BSNL TE to Nalanda TE

As per AGREEMENT NO. ENG-N-148/OFC/CONSTRUCTION/2018-19/37 dated 27.04.2019 you are hereby advised to carry out OFC Laying work in OFC route from RAJIR TE to SILEAS TE as per detail given below.

Sl.No.	PARTICULARS	Qty (Approx)
01	PLB PIPE LAIN BY Horizontal Boring (HDD)	2470 M
02	Excavating trenches up to a depth of 1.65 m and back filling the excavated trenches after laying the HDPE/PLB pipe with or without protection as per tender specification.	6.0KM
03	Laying of PLB/ HDPE Pipes Coils, Coupled with coupler & drawing of PP Nylon Rope through it	6.0KM
04	Cable laying by Pulling/blowing	9.0KM
05	Splicing termination of OF Cable	6 nos.
06	Digging of Pits for jointing chamber, supply and fixing of Pre Cast RCC chambers, clean sand filling, supply & placing of pre cast RCC slab and back filling of jointing Pit (Joint Chamber is of 100 cm X 110 cm X 50 cm) (Inner Dia x outer Dia x height)	6 nos.
07	Digging of Pits 1 meter toward jungle site on each manhole/joint chamber for fixing of route/joint indicator, fixing and concreting of routes/joint indicator, painting & sign writing of route/joint indicator (indicator)	45 nos.

Period: 60 days

Site Incharge :- Sh. VEDPRAKASH JTO TX (Rajgir)

Estimate No. FA/18/010017/02

Copy to :-

1. THE PGM PTD
2. THE DGM BRF/TX/PLG PTD
3. THE AGM PLG PTD
4. JTO TX RAJGIR
5. SDE STORES GARDANIBAGH PTD PATNA
6. OFFICE COPY

DET Nalanda, BIHARSARIF

DET, NALANDA
BSNL BIHAR SHARIF

DET Nalanda, BIHARSARIF

Registered & Corporate Office

Bharat Sanchar Bhavan, Harsh Chandra Mathur Lane Janpath, New Delhi-110 001 (CIN) U74899DL2000GOI10773

B. S. N. Bihar Sps.