TANK SCHEDULE :-

| TANK NO. | PRODUCT | CAPACITY |
|---|---|---|
| T1 | MS | 20KL |
| T2 | HSD | 20KL |
| T3 | HSD | 20KL |

PUMP SCHEDULE :-

| PRODUCT | NO.OF PUMP | NO.OF NOZZLE |
|---|---|---|
| MS | 2 | 4 |
| HSD | 2 | 4 |

SPECIFICATION NOTES- I

1. CERTIFIED THAT NO OTHER STRUCTURE WILL BE ERECTED NOR ANY OTHER SERVICE RENDERED EXCEPT THAT CONNECTED WITH PETROL PUMP WITHOUT THE PRIOR APPROVAL OF P.W.D.
2. CERTIFIED THAT THERE IS NO CROSSING WITHIN 300M BETWEEN THE TANGENT POINTS OF THE CURVES OF SIDE ROAD AND THAT OF THE FUEL FILLING CUM SERVICE STATION.
3. CERTIFIED THAT THERE IS NO OBJECTION FROM ROAD POINT OF VIEW FOR THE INSTALLATION OF THIS PUMP. THE PROPOSAL WILL NOT AFFECT THE FUTURE IMPROVEMENT OF THE ROAD.
4. CERTIFIED THAT NO OTHER PETROL PUMP EXISTS WITHIN THE DISTANCE OF 300M ON EITHER SIDE OF THE PLOT.
5. CERTIFIED THAT ALL CONDITIONS LAID DOWN BY THE GOVT. OF INDIA AND IRC FROM TIME TO TIME WITH REGARD TO THE LOCATION OF ROAD SIDE FUEL-FILLING CUM SERVICE STATIONS SHALL BE COMPLIED WITH & ENTIRE CONSTRUCTION WILL BE ON CORPORATION LAND.
6. NO DRAIN, SEWER OR STRUCTURE WITHIN 1.5M FROM UNDER GROUND TANKS.
7. SUCTION PIPES, UNDER DRIVEWAY HOUSED IN PIPE SLEEVES.
8. ELECTRIC FITTINGS CONFORM TO IS CODE NO- 2148 FOR DISPENSING PUMP ONLY.
9. DPS BOARD IS FIXED 1.5M HIGH FROM FLOOR LEVEL AND WILL NOT BE KEPT UNDER LOCK AND KEY.
10. 40MMØ VENT PIPES, 4M HIGH FROM GROUND LEVEL AND 4M CLEAR ALROUND. THE OPEN END OF VENT PIPE COVERED WITH TWO LAYERS OF NONE CORRODIBLE METAL WIRE GAUGE OF 11MESH PER LINIER CM.
11. 80MMØ FILL PIPES, TO BE PROVIDED 3.65M CLEAR ALL ROUND.
12. FIRE FIGHTING EQUIPMENT:-
    6 NOS. FOAM TYPE OF FIRE EXTINGUISHERS OF CAPACITY 9KG EACH FOR PETROLEUM FIRE, 2NOS CO2 TYPE FIRE EXTINGUISHERS OF CAPACITY OF 3KG EACH FOR FIGHTING ELECTRICAL FIRE AND 6NOS. OF FIRE BUCKETS FILLED WITH DRY SAND SHALL BE PROVIDED AT THE PETROL PUMP.
13. CERTIFIED THAT THERE WILL NOT BE ANY HINDRANCES FROM OVER HEAD HT LINES.
14. CERTIFIED THAT THE SURPLUS WATER WILL NOT BE DISPOSED OFF ON P.W.D LAND.
15. CERTIFIED THAT ALL THE CONDITIONS OF IRC-1983/2003 SHALL BE COMPLIED WITH.

IMPORTANT NOTES:-

1. CERTIFIED THAT THIS IS A NEW RETAIL OUTLET .
2. CERTIFIED THAT NO COURT CASE IS PENDING IN ANY COURT OF INDIA AGAINST THIS SITE/DEALERSHIP
3. CERTIFIED THAT ALL THE CLEARANCES/APPROVALS FROM MCP/IRC AND OTHER RELEVANT GOVT. DEPTT. SHALL BE OBTAINED.
4. CERTIFIED THAT ALL FACILITIES AS SHOWN IN THE DRAWING SHALL BE INSTALLED/PROVIDED AT ABOVE R/O.
5. STEEL CANOPY APPROVAL NO. CCE G-40 (NC) P-CANOPY dt. 26.07.89.

SPECIFICATIONS FOR TANKS:-

1. MS TANK OF 20KL CAPACITY FABRICATED AS PER DRG. APPROVED BY CCE VIDE LETTER NO. P-6(3) 51 DATED 23.01.2007.

SITE INFORMATION

| | |
|---|---|
| VILLAGE | CHANDAWALI |
| ROAD | SAMBHAL - HASANPUR ROAD |
| RAILWAY STATION | SAMBHAL |
| POLICE STATION | NAKHASA |
| TEHSIL | SAMBHAL |
| DISTRICT | SAMBHAL |
| GATA NO. | 151/2 |
| PIN CODE | 244302 |

| REV.NO. | DESCRIPTION | DATE | REV.BY | APP.BY |
|---|---|---|---|---|

INDIAN OIL CORPORATION LIMITED
(MARKETING DIVISION)
MORADABAD DIVISIONAL OFFICE
BEHIND KHWAJA FILLING STATION, NH-24, PAKBARA, MORADABAD-244102.

PROJECT:- PROPOSED RETAIL OUTLET BETWEEN KM. STONE NO.97-100, SH-51 ROAD,VILL.- CHANDAWALI, TEHSIL- SAMBHAL, DISTT- SAMBHAL (U.P.)

TITLE:- SITE & LAYOUT PLAN

DRAWN:- P.K. | DRG. NO:-SA/MDO/CHANDAWALI
CHKD:- | DATE:- 16.03.2017
APPRD:- | SCALE:- 1:200

SALES OFFICER | ASSTT. MGR. (TECH.) | MANAGER- RETAIL SALES | SO(TECH) | PREPARED BY:

मुरादाबाद वितरण कार्यालय
इंडियन ऑयल कॉर्पोरेशन लि० (एम.डी.)
पो. पाकबड़ा, मुरादाबाद-244102 (उ.प्र.)

अधिशासी अभियन्ता
प्रान्तीय खण्ड, लो०नि०वि०