

Name of work :- const. of stadium at Kolayat

Technical - Report

(i) Administrative & financial sanctioned

The Administrative & financial sanctioned  
Recd ~~at~~ from Adde collector (Vikas)  
D.R.D.A. Sikarwar vide letter no P 10 (1)/B.A.D.A/  
2001-02 / 1066-71 dated 29.01.2002 for  
Rs 10.00 lacs.

(ii) Specification :- following specifications adopted  
in the estimate.

- (i) cement concrete 1:5:10 (1 cement: 5 Bajri  
: 10 aggregate) in foundation & plinth
- (ii) R/R stone stone masonry in cement sand  
mortar 1:6 in foundation & plinth.
- (iii) Brick masonry 75 class in cement sand  
mortar 1:6 for super structure
- (iv) cement plaster 1:6 provided for finishing work
- (v) copings are also provided in 1:2:4,  
50 mm thick.
- (vi) whitewashing, snowchurn & iron grill  
gate etc taken in the estimate.

(iii) Agency :- Panchayat Samiti Kolayat

(iv) B.S.R :- Gramin Kalyan Nirdeshika - 2000

(v) Estimate cost :- Rs 10.00 lacs.

Signature  
Date

Signature  
सहायक अभियन्ता  
सा.नि.वि. जिला उप खण्ड  
कोलायत



5) नई दीवार पर सीमेंट का प्लास्टर  
 जो सीमेंट मसाला 1:6 हो हो, जोस  
 को साफ पुराई साहित्य पूरा काम, 20  
 मिमी मोटाई में हो तब में।

$$2 \times 550 \times 2.25 = 2475 \text{ sqm}$$

$$2475 \text{ sqm @ Rs } 60/- \text{ per sqm } = 1,48,500 = 00$$

6) सीमेंट कंक्रीट 1:2:4 (1 सीमेंट :  
 2 बजरी : 4 गिट्टी) की फर्श, किनारों  
 को गोला करना इत्यादि का काम 50 मिमी.  
 मोटाई में, 20 मिमी. गिट्टी की नाल साहित्य।

for Copings

$$1830 \times 0.45 \times 0.45 = 37.06 \text{ sqm}$$

$$467.650 \times 0.35 = 163.68 "$$


---


$$250.74 \text{ sqm}$$

$$20,475 = 00$$

$$250.74 \text{ sqm @ Rs } 102.00 \text{ per sqm}$$

7) पूरे से सफाई का काम, स्केफोल्डिंग साहित्य  
 नये काम 40 काम से काम 3 कोट में

$$2 \times 550 \times 0.05 = 55.00 \text{ sqm}$$

$$55.00 \text{ sqm @ Rs } 4.00 \text{ per sqm}$$

$$4,950 = 00$$

$$220 = 00$$

8) finishing cement plaster surface  
 with snow.chem

$$2 \times 550 \times 1.80 = 1980.00 \text{ sqm}$$

$$1980.00 \text{ sqm @ Rs } 15.00 \text{ per sqm}$$

$$29,700 = 00$$

9) अर. एम. जवाबदा की व्यवस्था करना, किता.  
 कुल 4.50 मी ऊंचाई तक लाली का काम नया

कील यंत्रण  
 देवनागरी/गुण/ 20 स्ल. (L.S.)  
 20 स्ल @ Rs 2104- per sl

$$42080 = 00$$

$$21,040 = 00$$

Hyament for T.S.Tap  
 Add 2% for 2% extra  
 10.00 lac  
 10.02, 4052

$$9,66,400 = 00$$

$$9,68,507 = 00$$

$$43,583 = 00$$

$$33,898 = 00$$


---


$$10.02, 4052$$

Say 10.00 lac

S.No. 11/11/11  
 Estimate by  
 (Rs. Ten lac only)

P.W.D. Bikaner

BIKANER

मौ.म. क. वि.स. उ. ए.स.  
 बीकानेर.

10.00 lac