

**Full Title of Project :- CONSTRUCTION OF LAKHWAN DAHANU HAWANU BHANGOT
RATHOL ANDRETA MERAMASIT ROAD KM 0/0 TO 8/010**

File No. :-

Date of Proposal :-

DETAIL OF MUCK/DEBRIES TO BE PRODUCED

**Name Of Work:- CONSTRUCTION OF LAKHWAN DAHANU HAWANU BHANGOT
RATHOL ANDRETA MERAMASIT ROAD KM 0/0 TO 8/010 TO BE CONSTRUCTED IN
DISTRICT MANDI STATE HIMACHAL PRADESH.**

Detail of quantity to be produced and used during the construction of road

Sr. No.	Description of items	Quantity
1	Total quantity to be produced during construction	43538.00
2	To be used for soling of road (6.5%),wearig of road (6.5%) and filling behind retaining walls of road (20%) total (33%)	14368.00
3	To be used for local use for construction of road average (total 33%)	14368.00
	Total quantity to be used (2+3) :-	28736.00
4	Net quantity to be dumped (1-(2+3))	14802.00
5	Soil factor 40%	5921.00
	G-Total (4+5) in cum :-	20723.00

Assistant Engineer
Chakkar Sub Division
HPPWD Ner Chowk

Executive Engineer,
Mandi Division No.II
HPPWD Mandi