

Full Title of Project :- CONSTRUCTION OF LAKHWAN DAHANU HAWANU BHANGOT RATHOL ANDRETA MERAMASIT ROAD KM 0/0 TO 8/010

File No. :-

Date of Proposal :-

ANNEXURE "C"

**STATEMENT SHOWING THE ROAD/CANAL/RAILWAY LINE TO BE CONSTRUCTED FROM CONSTRUCTION OF LAKHWAN DAHANU HAWANU BHANGOT RATHOL ANDRETA MERAMASIT ROAD
KM 0/0 TO 8/010**

S.No.	RD		Distance in mtr.			Width of right of way	Area of Road		Total Area in Sqm.	Name of village/Mahal and forest area nearly	Muck/ Debries to be produce (in cum) (Av. Height 1.5m)	Muck/ Debries to produce locally from 50%	Muck/Debries dumped locally for work 50%	Remarks
	From	To	Forest land (in mtr.)	Non Forest Land (in mtr.)	Total (in mtr.)		Forest land	Non Forest land						
1	0/0	0/090		90.00	90.00	5.68		511.00	511.00	Lakhwanu				
2	0/090	0/585	495.00		495.00	5.68	2812.00		2812.00					
3	0/585	0/710		125.00	125.00	5.68		710.00	710.00					
4	0/710	0/870	160.00		160.00	5.68	909.00		909.00					
5	0/870	1/180	310.00		310.00	5.68	1761.00		1761.00	Dahanu				
6	1/180	1/345		165.00	165.00	5.68		937.00	937.00					
7	1/345	1/700	355.00		355.00	5.68	2016.00		2016.00					
Existing Road km 1/700 to 3/120														
8	3/120	3/250	130.00		130.00	5.68	738.00		738.00	Hawanu				
9	3/250	3/265		15.00	15.00	5.68		85.00	85.00					
10	3/265	3/275	10.00		10.00	5.68	57.00		57.00					
11	3/275	3/570		295.00	295.00	5.68		1676.00	1676.00					
12	3/570	4/030	460.00		460.00	5.68	2613.00		2613.00					
13	4/030	4/545	515.00		515.00	5.68	2925.00		2925.00	Dahanu				
14	4/545	4/560		15.00	15.00	5.68		85.00	85.00					
15	4/560	4/780	220.00		220.00	5.68	1250.00		1250.00					
16	4/780	4/930		150.00	150.00	5.68		852.00	852.00					

S.No.	RD		Distance in mtr.			Width of right of way	Area of Road		Total Area in Sqm.	Name of village/Muhal and forest area nearly	Muck/ Debries to be produce (in cum) (Av. Height 1.5m)	Muck/ Debries to produce locally from 50%	Muck/Debries dumped locally for work 50%	Remarks
	From	To	Forest land (in mtr.)	Non Forest Land (in mtr.)	Total (in mtr.)		Forest land	Non Forest land						
	Existing Road km 4/930 to 6/410													
17	6/410	6/425	15.00		15.00	5.68	85.00		85.00	Rathol				
18	6/425	6/600		175.00	175.00	5.68		994.00	994.00					
19	6/600	6/950	350.00		350.00	5.68	1988.00		1988.00					
20	6/950	6/975	25.00		25.00	5.68	142.00		142.00	Merajitpur				
21	6/975	7/065		90.00	90.00	5.68		511.00	511.00					
22	7/065	7/225	160.00		160.00	5.68	909.00		909.00					
23	7/225	7/345		120.00	120.00	5.68		682.00	682.00					
24	7/345	7/595	250.00		250.00	5.68	1420.00		1420.00					
25	7/595	7/625		30.00	30.00	5.68		170.00	170.00					
26	7/625	7/955	330.00		330.00	5.68	1874.00		1874.00					
27	7/955	7/975		20.00	20.00	5.68		114.00	114.00					
28	7/975	8/010	35.00		35.00	5.68	199.00		199.00					
		Total:-	3820.00	1290.00	5110.00		21698.00	7327.00	29025.00		43538.00	21769.00	21769.00	

Assistant Engineer
Chakkar Sub Division
HPPWD Ner Chowk

Executive Engineer,
Mandi Division No.II
HPPWD Mandi