

DETAIL OF AREA OF APPROACHES	
DETAILS OF APPROACH A:-	**DETAILS OF APPROACH B:-**
AREA OF A1 = 17.03X1.50 = 25.54SQ.M AREA OF A2 = 1/2X4.22X0.81 - 2/3X4.37X0.19 = 1.16SQ.M AREA OF A3 = 5.50X13.43 = 73.86SQ.M AREA OF A4 = 1/2X6.89X0.67 = 2.31SQ.M AREA OF A5 = 1/2X57.17X5.50 = 157.21SQ.M	AREA OF B1 = 12.00X1.50 = 18.00SQ.M AREA OF B2 = 1/2X6.01X1.50 - 2/3X6.25X0.38 = 2.92SQ.M AREA OF B3 = 5.50X20.17 = 110.93SQ.M AREA OF B4 = 5.50X49.84 = 274.125Q.M AREA OF B5 = 1/2X5.50X30.00 = 82.50SQ.M
TOTAL AREA OF APPROACH A: = 260.08SQ.M	**TOTAL AREA OF APPROACH B: = 488.47SQ.M**
DETAILS OF APPROACH C = 57.00X5.50 = 313.50SQ.M	
TOTAL AREA OF APPROACHES = 1062.05SQ.M. (0.1062HA) **FOREST AREA = 0.1062HA.** **NON FOREST AREA 0.2599 HA.**	

BUILDING DETAILS		
Sr. No.	TYPE	SIZE
1	SALES ROOM	2.625X2.805M
2	AUTOMATION	1.20X0.75M
3	CASH ROOM	1.31X1.80M
4	WATER COOLER	1.31X0.865M
5	LADIES TOILET	1.20X1.80M
6	GENTS TOILET	1.80X1.20M
7	ELEC./PANEL RM.	1.80X1.20M
8	LUBE STORE	1.80X2.245M





VILLAGE	LOHANI
KHASRA NO.	100//23/2/2,24/2
KHEWAT NO.	880 MIN//802
KHATAUNI NO.	1007,1035
NEAREST POLICE STATION	BHIWANI
NEAREST RAILWAY STATION	BHIWANI
TEHSIL	BHIWANI
DISTT.	BHIWANI
PIN CODE	127030
STATE	HARYANA



SEC. DETAIL OF 1M SPAN R.C.C. SLAB CULVERT AS PER IRC: SP: 13-2004
SCALE 1:50



TYPICAL X-SECTION OF APPROACH ROAD
SCALE 1:30



X-SECTION OF DRAIN WITH IRON GRATING
SCALE 1:20



HARVESTING SYSTEM



SECTION OF COMPOUNDWALL
SCALE 1:30



SECTION OF KERB WALL
SCALE 1:30



SECTION OF CANOPY
SCALE 1:100

BHARAT PETROLEUM CORPN. LTD.

LAYOUT & LOCATION PLAN OF PROPOSED RETAIL OUTLET AT *VILLAGE LOHANI*, ON BHIWANI - LOHARU ROAD, (OLD SH-14) NEW NH=709-E, CH. 135.098 TO 135.150 (RHS), TEHSIL & DISTT. BHIWANI (HARYANA). PIN CODE 127030

NOTES

1. CERTIFIED THAT ALL THE TRAFFIC SIGNS ARE AS PER IRC: 67-2001 AND IRC: SP 55-2001.
2. CERTIFIED THAT THERE IS NO ANY EXISTING BARRIER OF SALES TAX ETC WITHIN 1 K.M. RANGE.
3. ALL THE STANDARD CONDITIONS HAVE BEEN SATISFIED.
4. ALL THE DIMENSIONS ARE IN METRES UNLESS OTHER -WISE SPECIFIED.
5. STORM WATER OF OUR BUILDING WILL NOT DISTURB NH 709-E.
6. 1.00M WIDE SLAB TYPE CULVERT PROVIDED BY US.
7. LEVEL OF BUILDING KEPT 2% BELOW ON NH ROAD LEVEL.
8. WE WILL NOT DEMAND ANY GAP IN CENTRAL VERGE IN FRONT. OF OUR PLOT.
9. THE MORT&H INSTRUCTION SHELL NOT VOILATED.
10. CERTIFIED THAT THE ALL MORT&H CONDITIONS HAVE BEEN SPECIFIED.
11. CERTIFIED THAT WE WILL APPLY THE CASE FOR RENEWEL AFTER 5YEAR FROM THE DATE OF ISSUE.
12. WE WILL PAY THE NECESSORY FEE FOR THE USE OF NH LAND WHENEVER ASKED BY THE AUTHORITIES.
13. 5.50M WIDE ACCELERATION/DECELERATION LANES CONSTRUCT/MENTAINED BY THE BPCL.

(A) -Fuel Station Ahead at 1km & 500m	(G) -Compulsory Direction Control
(B) -Fuel Station	(H) -No Right Turn
(C) -Fuel Station Ahead	(I) -Fuel Station
(D) -Give Way	(J) - Toilet
(E) -One way	(K) - Drinking Water
(F) -No Entry	

DWG.NO. : TCS/BPCL/HR-1560

DATE : REV-14-06-2018

DRAWN BY:-

THE CYBER SPACE
Plot no. 2, Ist floor,
Sarai Sadhu Ram, G.T. Road,
Puttighar Chowk, Amritsar.
0183-5018272, +919876103744
E-mail:- thecyberspace5@gmail.com

APPLICANT

CONSULTANT

HIGHWAY ADMINISTRATOR