

Full Title of the Project :- CONSTRUCTION OF TANDA KOHLA TIKKARI KAWAL KOTHI SIDHKOTHI VIA BABA BALAK NATH MANDIR THAPLA DARI KA NAL SIDHYANI ROAD KM 0/0 TO 11/340

File No: \_\_\_\_\_

Date of Proposal: \_\_\_\_\_

### JUSTIFICATION FOR THE LOCATING THE PROJECT IN FOREST AREA

The proposed alignment for the said road has been carefully finalized after considering a total No. of three alternate alignment in all the cases a portion of the road shall pass through the forest area. The first alignment was considered with its commencing point at km 2/700 from Ratti Meramsit Road of CONSTRUCTION OF TANDA KOHLA TIKKARI KAWAL KOTHI SIDHKOTHI VIA BABA BALAK NATH MANDIR THAPLA DARI KA NAL SIDHYANI ROAD KM 0/0 TO 11/340. In this case the total length of the road worked out to be 11/340 km out of which 3605 meter length falls in forest area which involves 2.2876 hect.

The 2<sup>nd</sup> alignment is considered with its commencing point at km 3/505 from Ratti Meramsit Road of CONSTRUCTION OF TANDA KOHLA TIKKARI KAWAL KOTHI SIDHKOTHI VIA BABA BALAK NATH MANDIR THAPLA DARI KA NAL SIDHYANI ROAD KM 0/0 TO 12/145. In this case the total length of the road worked out to be 12/145 km out of which 4410 meter length falls in forest area which involves 2.7449 hect.

The 3<sup>rd</sup> alignment is considered with its commencing point at km 3/125 from Ratti Meramsit Road of CONSTRUCTION OF TANDA KOHLA TIKKARI KAWAL KOTHI SIDHKOTHI VIA BABA BALAK NATH MANDIR THAPLA DARI KA NAL SIDHYANI ROAD KM 0/0 TO 11/765. In this case the total length of the road work out to be 11/765 km out of which 4030 meter road length passes through the forest area as such the forest area involved stood 2.5290 hect.

The 2<sup>nd</sup> and 3<sup>rd</sup> alignment has to be rejected because of extreme road length and more forest area involved. It involved more number of fully grown trees as compared to second alignment.


The alignment No. 1<sup>st</sup> serve more habitation rather than alignment No. 2<sup>nd</sup> & 3<sup>rd</sup> Contrary above short coming of alignment 2<sup>nd</sup> and 3<sup>rd</sup> alternate alignment No.1<sup>st</sup> is shortest in length involves lesser number of trees and leaser forest area.

Therefore keeping in view the above certain point in the favour of alignment No.1<sup>st</sup> the construction of road in this alignment would save from huge destruction of damages to the forest as well as to environment and beautiful feature of the valley.

Ultimately for the 1<sup>st</sup> alignment is finalized and adopted for the construction of proposed road which is most economical feasible best and is over all public interest as well easy for construction in all respect.

Assistant Engineer  
Chakkar Sub Division  
HPPWD Ner Chowk

  
Divisional Forest Officer  
Forest Division Mandi (H.P.)

  
Executive Engineer  
Mandi Division No.II  
HPPWD Mandi

  
Divisional Forest Officer  
Suket Forest Division  
Sunder Nagar (H.P.)-174401